


Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 No. Market  
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above Section Plat

Russell County, Sec. 34 Twp. 12 Rgs. 15 (E) W (W)  
Location as "NE/CNW/SW" or footage from lines N/2 NW SW  
Lease Owner Shields Oil Producers, Inc.  
Lease Name Davis "B" Well No. 1  
Office Address Shields Building, Russell, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry hole  
Date well completed April 7, 1969  
Application for plugging filed April 7, 1969  
Application for plugging approved April 7, 1969  
Plugging commenced April 7, 1969  
Plugging completed April 7, 1969  
Reason for abandonment of well or producing formation Dry hole

If a producing well is abandoned, date of last production 19\_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Donald Truan  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3,260 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	245'	Cmtd. w/175 sax

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Fill hole w/ heavy mud  
Set bridge plug @ 480'  
Dump 40 sax cement on plug thru 4 1/2" drill pipe  
Fill hole w/ heavy mud to 240'  
Set bridge plug @ 240'  
Dump 25 sax cement on plug thru 4 1/2" drill pipe  
Fill hole w/ heavy mud to 40'  
Set bridge plug @ 40' w/ 1/2 sax hulls on plug  
Dump 10 sax cement on plug to cellar

RECEIVED  
STATE CORPORATION COMMISSION  
APR 25 1969  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Shields Drilling Co., Inc.  
Address Shields Building, Russell, Kansas

STATE OF Kansas, COUNTY OF Russell, ss.  
R. J. Shields (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) RJ Shields  
Shields Building, Russell, Kansas  
(Address)

SUBSCRIBED AND SWORN to before me this 24th day of April, 1969

My commission expires May 26, 1971

Leta Phillips  
Notary Public.



# Shields


Russell, Kansas

15-167-20305-00-00

## WELL LOG

Operator: Shields Oil Producers, Inc.  
 Well: Davis "B" #1  
 Commenced: March 31, 1969  
 Completed: April 7, 1969  
 Contractor: Shields Drilling Co., Inc.

Well Description: N/2 NW SW  
 Sec. 34-12S-15W  
 Russell County, Kansas



CASING RECORD		
Size	Run	Pulled
8 5/8"	245'	Cmtd. w/ 175 sax

Elevation: 1,792' RB

Treatment:

Production: D & A

Tops:	
Heebner	2,907'
Toronto	2,927'
Lansing-KC	2,955'
Rew. Arbuckle	3,227'
Arbuckle	3,247'

..... Figures Indicate Bottom of Formations .....

Rock and shale	100'
Shale and shells	252'
Shale and sand	500'
Redbed	860'
Anhydrite	895'
Shale and shells	1,285'
Shale and salt	1,460'
Shale and lime	1,735'
Lime	1,900'
Lime and shale	2,685'
Lime	2,905'
Lime and shale	2,995'
Lime	3,260' RTD

### NOTES

- DST #1 2,961' - 2,995' Tool open 30 min. w/ very weak blow. Recovered 65' VSO & GCM. IBHP-670#, IFP-0#, FFP-0#, FBHP-641#/30 min.
- DST #2 2,996' - 3,020' Tool open 2 hrs. w/ good blow. Recovered 480' salt water. IBHP-520#, IFP-50#, FFP-190#, FBHP-0#/30 min.
- DST #3 3,080' - 3,155' Tool open 2 hrs. w/ good blow. Recovered 510' watery mud. IBHP-830#, IFP-90#, FFP-200#, FBHP-690#/30 min.

RECEIVED  
 STATE CORPORATION COMMISSION  
 4-25-1969  
 APR 25 1969  
 CONSERVATION DIVISION  
 Wichita, Kansas