


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

15-167-00114-00-00
WELL PLUGGING RECORD

Russell County, Sec. 34 Twp. 12S Rge. (E) 15 (W)

NORTH



Locate well correctly on above
Section Plat

Location as "NE/CNW%SW%" or footage from lines C NE NE NE
Lease Owner Cooperative Refinery Ass'n.
Lease Name Davis "Q" Well No. 1
Office Address Box 765 Gt. Bend, Ks.
Character of Well (completed as Oil, Gas or Dry Hole) Dry hole
Date well completed 9-29 19 59
Application for plugging filed 9-30 19 59
Application for plugging approved Verbal permission obtained 19
Plugging commenced 9-30 19 59
Plugging completed 9--30 19 59
Reason for abandonment of well or producing formation Dry hole

If a producing well is abandoned, date of last production _____ 19____

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes, verbal permission

Name of Conservation Agent who supervised plugging of this well Eldon Petty

Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3275 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	457'	-0-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with heavy mud to 440', set bridge plug at 440',
dumped 20 sx. cement thru drill pipe on plug. Filled with
heavy mud to 180', set bridge plug at 180', dumped 20 sx.
cement thru drill pipe on plug, filled with heavy mud to 40',
set bridge plug at 40', dumped 10 sx. cement on plug to cellar.
Complete

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Shields Drlg. Company
Address Russell, Kansas

STATE OF KANSAS, COUNTY OF BARTON, ss.
Marvin D. Sullivan (employee of owner) or (owner or operator) of the above-described
well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the
above-described well as filed and that the same are true and correct. So help me God.

(Signature) Marvin D. Sullivan
Great Bend, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 30 day of September, 19 59

My commission expires Sept. 24, 1960

Yvonne Adams Notary Public.

RECEIVED
STATE CORPORATION COMMISSION
10-3-1959
OCT 3 1959

CONSERVATION DIVISION
Wichita, Kansas

15-167-00114-00-00
DRILLERS LOG

Davis "Q" #1

Elevation: 1808' D.F.

Loc: C NE NE NE
Sec: 34-12S-15W
Russell County, Kansas
Operator: Cooperative Refinery Ass'n.
Contractor: Shields Drlg. Company

Casing: 8 5/8" @ 457' w/
250 sx.
Comm: 9-20-59 Comp: 9-30-59
R.T.D. 3275'

<u>From</u>	<u>To</u>	<u>Formation</u>
0	340	Rock, shale, shells
340	440	Sand, pyrite and shale
440	457	Sandy shale
457	1925	Lime and shale
1925	2055	Lime
2055	2163	Lime with shale
2163	2815	Lime and shale
2815	3275	Lime
3275		R.T.D.

(STATE OF KANSAS)

(COUNTY OF BARTON)

I hereby certify that the above is a true and correct copy of the log on the Davis "Q" #1 well, located C NE NE NE of Section 34-12S-15W, Russell County, Kansas.

M. D. Sullivan

Subscribed and sworn to before me this 1 day of October 1959.

Y. Conrad Adams

My commission expires: September 24, 1960.

RECEIVED
STATE CORPORATION COMMISSION
10-3-1959
OCT 3 1959
CONSERVATION DIVISION
Wichita, Kansas