


Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 No. Market  
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above  
Section Plat

Russell County. Sec. 35 Twp. 12 Rge. 15 (E) W (W)  
Location as "NE/CNW%SW%" or footage from lines NW SW SW  
Lease Owner Shields Oil Producers, Inc.  
Lease Name Holland "C" Well No. 1  
Office Address Shields Bldg., Russell, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry hole  
Date well completed 2-24 19 67  
Application for plugging filed 2-24 19 67  
Application for plugging approved 2-24 19 67  
Plugging commenced 2-24 19 67  
Plugging completed 2-24 19 67  
Reason for abandonment of well or producing formation \_\_\_\_\_

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Donald Truan  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3,195 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	271'	Cmtd w/ 180 sax

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Fill w/ heavy mud to 265'  
Set bridge plug @ 265' w/ 1/4 sax hulls on plug  
Dump 25 sax cement on plug thru 4 1/2" drill pipe  
Fill w/ heavy mud to 40'  
Set bridge plug @ 40' w/ 1/2 sax hulls on plug  
Dump 10 sax cement on plug to cellar

3-28-1967

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Shields Drilling Co., Inc.  
Address Shields Bldg., Russell, Kansas

STATE OF KANSAS, COUNTY OF RUSSELL, ss.  
R. J. Shields (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God

(Signature) R. J. Shields  
Shields Bldg., Russell, Kansas  
(Address)

SUBSCRIBED AND SWORN to before me this 23 rd day of March, 19 67.

My commission expires May 26, 1967

Keith Phillips  
Notary Public.



# Shields


15-167-2004-00-00

Russell, Kansas

## WELL LOG

Operator: Shields Oil Producers, Inc.  
 Well: Holland "C" #1  
 Commenced: February 17, 1967  
 Completed: February 24, 1967  
 Contractor: Shields Drilling Co., Inc.

Well Description: NW SW SW  
 Sec. 35-12S-15W  
 Russell Co., Kansas



**CASING RECORD**

Size	Run	Pulled
8 5/8"	271'	Cmtd w/ 180 sax

Elevation: 1, 717' RB  
 Treatment:

Production: D & A

Tops:

Heebner	2, 854'
Toronto	2, 875'
Lansing-KC	2, 907'
Arbuckle	3, 176'

..... Figures Indicate Bottom of Formations .....

Sand, shale & shells	277'
Shale, shells, pyrite & sand	355'
Shale, shells, redbed	784'
Anhydrite	820'
Shale, shells & salt	1, 400'
Shale & lime	1, 715'
Lime	1, 875'
Lime & shale	2, 640'
Lime	3, 195' R T D

### NOTES

DST #1	2, 910' - 51'	Tool open 1 hr w/ weak blow for 5 min. Recovered 15' mud. IBHP-472#, IFP-0#, FFP-0#, FBHP-380#/20 min.
DST #2	3, 172' - 82'	Tool open 1 hr w/ weak blow for 20 min. Recovered 10' mud, IBHP-1, 000#, IFP-0#, FFP-0#, FBHP-unknown
DST #3	3, 172' - 95'	Tool open 1 hr w/ weak blow for 5 min. Recovered 10' mud. IBHP-780#, IFP-0#, FFP-0#, FBHP-680#/20 min.

**RECEIVED**  
 STATE GEOLOGICAL COMMISSION

3-28-1967  
 MAR 28 1967

CONSERVATION DIVISION  
 Wichita, Kansas