

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
March 2009
Type or Print on this Form
Form must be Signed
All blanks must be Filled

21994-00-00

OPERATOR: License #: 33405
Name: ANSTINE & MUSGROVE INC
Address 1: PO BOX 391
Address 2: _____
City: PONCA CITY State: OK Zip: 74602 + _____
Contact Person: GARY ANSTINE
Phone: (620) 441-8165
Type of Well: (Check one) Oil Well Gas Well OG D&A Cathodic
 Water Supply Well Other: SWD SWD Permit #: D 21634
 ENHR Permit #: _____ Gas Storage Permit #: _____
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)
MISSISSIPPI Depth to Top: .3058 Bottom: .3089 T.D. .3102
_____ Depth to Top: _____ Bottom: _____ T.D. _____
_____ Depth to Top: _____ Bottom: _____ T.D. _____

API No. 15 - 035
Spot Description: SW-SE-NW Sec. 25 Twp. 33 S. R. 4 East West
2870 3007 Feet from North / South Line of Section
3.630 Feet from East / West Line of Section
Footages Calculated from Nearest Outside Section Corner:
 NE NW SE SW
County: COWLEY
Lease Name: MOSKWE MOSLER Well #: 2
Date Well Completed: 12/7/78
The plugging proposal was approved on: 4/10/09 (Date)
by: DUANE KRUEGER (KCC District Agent's Name)
Plugging Commenced: 4/13/09
Plugging Completed: 4/13/09

Show depth and thickness of all water, oil and gas formations.

| Oil, Gas or Water Records | | Casing Record (Surface, Conductor & Production) | | | |
|---------------------------|-------------|---|--------|---------------|------------|
| Formation | Content | Casing | Size | Setting Depth | Pulled Out |
| STALNAKER | WATER | SURFACE | 8 5/8" | 193 | 0 |
| MISSISSIPPI | OIL & WATER | CASING | 4 1/2" | 3089 | 0 |
| | | | | | |
| | | | | | |

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

SET CIBP @ 1875, SPOTTED 10 SACKS CEMENT ON PLUG, PERFORATED 4 1/2" CASING @ 300' AND CIRCULATED CEMENT TO SURFACE, WELDED CAP 4 1/2" 4' BELOW GROUND LEVEL.

KANSAS CORPORATION COMMISSION

APR 29 2009
RECEIVED

Plugging Contractor License #: 31539 Name: SAMS WELL SERVICE
Address 1: PO BOX 391 Address 2: _____
City: PONCA CITY State: OK Zip: 74602 + _____
Phone: (620) 441-3943
Name of Party Responsible for Plugging Fees: ANSTINE & MUSGROVE INC
State of KANSAS County, COWLEY, ss.
ROBERT J ANSTINE Employee of Operator or Operator on above-described well,
(Print Name)

being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

Signature: Robert J Anstine

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202



CONSOLIDATED
Oil Well Services, LLC

REMIT TO
Consolidated Oil Well Services, LLC
Dept. 970
P.O. Box 4346
Houston, TX 77210-4346

MAIN OFFICE
P.O. Box 884
Chanute, KS 66720
620/431-9210 • 1-800/467-8676
FAX 620/431-0012

INVOICE

Invoice # 229385

Invoice Date: 04/10/2009 Terms: 0/30,n/30

Page 1

ANSTINE & MUSGROVE OIL CO
P.O. BOX 391
PONCA CITY OK 74602
(580)762-6355

MOSLER #2
20565
04-07-09

| Part Number | Description | Qty | Unit Price | Total |
|-------------|--------------------------|--------|------------|---------|
| 1131 | 60/40 POZ MIX | 128.00 | 10.7000 | 1369.60 |
| 1118A | S-5 GEL/ BENTONITE (50#) | 500.00 | .1600 | 80.00 |

| Description | Hours | Unit Price | Total |
|---------------------------------|--------|------------|--------|
| 290 P & A OLD WELL | 1.00 | 590.00 | 590.00 |
| 290 EQUIPMENT MILEAGE (ONE WAY) | 60.00 | 3.45 | 207.00 |
| 442 TON MILEAGE DELIVERY | 360.96 | 1.16 | 418.71 |

Chg for Mosler 3A
RJC

KANSAS CORPORATION COMMISSION

APR 29 2009

RECEIVED

PAID
CHECK NO. 11434
AMOUNT \$ 2749.39
DATE 4-13-09

| | | | | | | | |
|--------|---------|-----------|-----|---------|---------|----|---------|
| Parts: | 1449.60 | Freight: | .00 | Tax: | 84.08 | AR | 2749.39 |
| Labor: | .00 | Misc: | .00 | Total: | 2749.39 | | |
| Sublt: | .00 | Supplies: | .00 | Change: | .00 | | |

Signed _____ Date _____



CONSOLIDATED
Oil Well Services, LLC

ENTERED

TICKET NUMBER 20565
LOCATION 5/Dorado #80
FOREMAN Jim Thomas

PO Box 884, Clarita, KS 66720
620-431-9210 or 800-467-8676

FIELD TICKET & TREATMENT REPORT
CEMENT

| DATE | CUSTOMER # | WELL NAME & NUMBER | SECTION | TOWNSHIP | RANGE | COUNTY |
|---------------------------------------|------------|--------------------|---------|----------|---------|--------|
| 4-7-09 | 1098 | Master #2 | | | | Cowley |
| CUSTOMER Anstine & Musgrave Oil Co | | | TRUCK # | DRIVER | TRUCK # | DRIVER |
| MAILING ADDRESS P.O. Box 391 | | | 290 | Gene | | |
| CITY Ponca City | | | 442 | Bobby | | |
| STATE OK | | | | | | |
| ZIP CODE 74601 | | | | | | |

JOB TYPE Plug HOLE SIZE _____ HOLE DEPTH _____ CASING SIZE & WEIGHT 4 1/2
 CASING DEPTH _____ DRILL PIPE _____ TUBING _____ OTHER _____
 SLURRY WEIGHT _____ SLURRY VOL _____ WATER gal/sk _____ CEMENT LEFT in CASING _____
 DISPLACEMENT _____ DISPLACEMENT PSI _____ MIX PSI _____ RATE _____

REMARKS: Solidly Mixing Rig up to 2 3/4" tubing Pump 10 sks 60/40 per 4% gel bed to 18 1/2 hrs. Spot on top of C.T.D.P. Pull tubing up & packed off head, & shut in tube. Pumped 118 sks 60/40 per 4% gel down the 4 1/2" circulated in the cellar. Pulled tubing out & taped off. Wash up & rig down.

| ACCOUNT CODE | QUANTITY or UNITS | DESCRIPTION of SERVICES or PRODUCT | UNIT PRICE | TOTAL |
|-------------------------------|-------------------|------------------------------------|------------|---------|
| 5405A | 1 | PUMP CHARGE | 590.00 | 590.00 |
| 5406 | 60 | MILEAGE | 3.45 | 207.00 |
| 1131 | 138 sks | 60/40 per | 10.70 | 1369.60 |
| 113A | 500 lbs | gel | .16 | 80.00 |
| 5407A | 6.01 TONS | 60 miles Bulk Del. | 1.16 | 418.71 |
| KANSAS CORPORATION COMMISSION | | | | |
| APR 29 2009 | | | | |
| RECEIVED | | | | |
| | | | | 265.51 |
| | | | | 84.08 |
| | | | | 2749.39 |

Revin 3737 AUTHORIZATION [Signature] TITLE Prod. Supt DATE 4-7-09
 SALES TAX ESTIMATED TOTAL 2749.39