


STATE OF KANSAS  
STATE CORPORATION COMMISSION

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

15-051-00740-00-00  
WELL PLUGGING RECORD

NORTH



Locate well correctly on above  
Section Plat

Ellis County, Sec. 1 Twp. 12S Rge. 16 (E) W (W)  
Location as "NE/CNW%SW%" or footage from lines SW SW SW  
Lease Owner Frontier Oil Company  
Lease Name National Loan Company Well No. 1  
Office Address 580 Fourth National Bank Building-Wichita, Ks.  
Character of Well (completed as Oil, Gas or Dry Hole) D & A  
Date well completed January 31 19 58  
Application for plugging filed January 31 19 58  
Application for plugging approved January 31 19 58  
Plugging commenced January 31 19 58  
Plugging completed January 31 19 58  
Reason for abandonment of well or producing formation D & A

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty  
Producing formation Depth to top Bottom Total Depth of Well Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| FORMATION | CONTENT | FROM | TO | SIZE   | PUT IN | PULLED OUT |
|-----------|---------|------|----|--------|--------|------------|
|           |         |      |    | 8 5/8" | 207'   | -0-        |
|           |         |      |    |        |        |            |
|           |         |      |    |        |        |            |
|           |         |      |    |        |        |            |
|           |         |      |    |        |        |            |
|           |         |      |    |        |        |            |
|           |         |      |    |        |        |            |
|           |         |      |    |        |        |            |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole with heavy mud. Set bottom plug @ 500'.  
Put 20 sacks of cement through drill pipe. Filled  
hole with heavy mud to 200'. Set middle plug @ 200'.  
Put 20 sacks of cement through drill pipe on middle  
plug. Filled with heavy mud to 40'. Set top plug  
@ 40'. Put 1/2 sack Hulls and 10 sacks on top plug.  
Filled to base of collar.

STATE CORPORATION COMMISSION  
2-5-1958  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Red Tiger Drilling Company  
Address Box 173 Russell, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.  
George A. Angle (employer or owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) George A. Angle  
580 Fourth National Bank Building-Wichita (Address)

SUBSCRIBED AND SWORN to before me this 4th day of February, 19 58

My commission expires 11-17-58 Notary Public.

PLUGGING  
FILED SEC 1 T 12 R 16  
BOOK PAGE 80 LINE 35

DRILLERS LOG

No. 1 National Loan Company

CASING RECORD: 8-5/8" @ 207# w/135 sx cement  
 COMPANY: Frontier Oil Company  
 CONTRACTOR: Red Tiger Drilling Co.  
 COMMENCED: January 22, 1958  
 COMPLETED: January 31, 1958  
 TOTAL DEPTH: 3417 (-1565)

DESCRIPTION: SW SW SW  
 1-12S-16W  
 Ellis  
 County  
 Kansas  
 ELEVATION: 1849 DF  
 1852 RB

| <u>FORMATION</u>          | <u>FROM</u> | <u>TO</u> | <u>REMARKS</u> |
|---------------------------|-------------|-----------|----------------|
| Post Rock and Shells Sand | 0           | 40        |                |
| Blue Shale and Shells     | 40          | 65        |                |
| Shale, Shell and Sand     | 65          | 207       |                |
| Shale and Shells          | 207         | 685       |                |
| Anhydrite                 | 685         | 1009      |                |
| Shale and Shells          | 1009        | 1050      |                |
| Shale and Lime            | 1050        | 1870      |                |
| Lime                      | 1870        | 3094      |                |
| Lime and Shale            | 3094        | 3115      |                |
| Lime                      | 3115        | 3205      |                |
| Lime                      | 3205        | 3417      |                |

I certify that this is a true and correct copy of the above log to the best of my knowledge.

FRONTIER OIL COMPANY

George A. Angle  
George A. Angle

Subscribed and sworn to before me this 4<sup>th</sup> day of February, 1958.

Maryne Head  
Notary Public

My Commission Expires:  
11-17-58

DRILLING  
 NE 1/4 12 R. 16W  
 PAGE 80 LINE 35

2-5-1958