


Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above  
Section Plat

Ellis County. Sec. 1 Twp. 12S Rge. 16W (#) (W)  
Location as "NE/CNW/SW" or footage from lines NE SW SE  
Lease Owner Hinkle Oil Company  
Lease Name Ruggles Well No. 1  
Office Address 1016 Union Center, Wichita, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed 12-19-64 19  
Application for plugging filed 12-19-64 19  
Application for plugging approved 12-19-64 19  
Plugging commenced 12-19-64 19  
Plugging completed 12-19-64 19  
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty, Hays, Kansas  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3410 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	262'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Plug @ 450' with 20 sacks cement  
Plug @ 240' with 20 sacks cement  
Plug @ 40' with 1/2 sack bulls and 10 sks. cement

RECEIVED  
STATE CORPORATION COMMISSION  
12-28-1964  
DEC 28 1964

CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Leben Drilling, Inc.  
Address Box 486, Great Bend, Kansas 67530

STATE OF KANSAS, COUNTY OF BARTON ss.

Leslie Kite (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Leslie Kite  
P. O. Box 486, Great Bend, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 23rd day of December, 19 64

My commission expires April 1, 1967

Ulanda Nichols  
Ulanda Nichols Notary Public.

15-051-01538-00-00

DRILLER'S LOG

COMPANY: Hinkle Oil Company  
 CONTRACTOR: LEBEN DRILLING, INC.  
 FARM: RUGGLES #1  
 LOCATION: NE SW SE Sec. 1-12S-16W  
 ELLIS COUNTY, KANSAS  
 COMMENCED: 12-11-64  
 COMPLETED: 12-19-64

0	15	Soil & Clay
15	145	Blue Shale
145	170	Sand & Shale
170	262	Shale
262	375	Shale & Shells
375	510	Shale & Sand
510	605	Sand
605	955	Redbed
955	994	Anhydrite
994	1590	Shale & Shells
1590	1850	Shale with Lime Streaks
1850	2775	Lime & Shale
2775	3410	Lime
	<u>3410</u>	<u>Rotary Total Depth - D. &amp; A.</u>

RECEIVED  
 STATE CORPORATION COMMISSION  
 12-28-1964  
 DEC 28 1964  
 CONSERVATION DIVISION  
 Wichita, Kansas

Set 8 5/8" used surface casing @ 262' with 170 sacks HA5 50-50 Posmix

I, Leslie Kite, do hereby certify that the above and foregoing is a true and correct copy of the log of the Ruggles #1 well, located NE SW SE of Section 1, Township 12 South, Range 16 West, Ellis County, Kansas, as reflected by the records of Leben Drilling, Inc.

*Leslie Kite*  
 \_\_\_\_\_  
 Leslie Kite

STATE OF KANSAS )  
 ) SS  
 COUNTY OF BARTON )

Subscribed and sworn to before me, a Notary Public, in and for Barton County, Kansas, this 23rd day of December, 1964.

*Ulanda Nichols*  
 \_\_\_\_\_  
 Ulanda Nichols

My Commission Expires  
 April 1, 1967