

STATE OF KANSAS
STATE CORPORATION COMMISSION

15-051-00780-00-00
WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

Ellis County, Sec. 8 Twp. 12 Rge. 16 (E) (W)

Location as "NE/CNW&SW&" or footage from lines SW SW NW

Lease Owner Isern Drilling Company

Lease Name Windholz Well No. 1

Office Address Box 45, Ellinwood, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed May 31, 1954 19

Application for plugging filed May 31, 1954 19

Application for plugging approved May 31, 1954 19


Plugging commenced May 31, 1954 19

Plugging completed May 31, 1954 19

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well Eldon Petty

Producing formation Depth to top Bottom Total Depth of Well 3476 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
	Surface Pipe	0	160'	8-5/8"	160'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole with heavy mud to 155'.
Set bridge plug at 155', ran 20 sacks
cement 155' up. Filled hole with heavy
mud to 40'. Set bridge plug at 40', ran
10 sacks cement 40' to base of cellar.

6-3-1954

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Isern Drilling Company

Address Box 45, Ellinwood, Kansas

STATE OF KANSAS, COUNTY OF BARTON
I. M. M. Shropshire (employee of owner) or (owner/operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) I. M. M. Shropshire

Lyons, Kansas

(Address)

SUBSCRIBED AND SWORN TO before me this 1st day of June, 1954

My commission expires Feb. 10, 1955.

George A. Meyer
Notary Public.

PLUGGING
FILE SEC 8 TWP 12 RGE 16 W
BOOK PAGE 38 LINE 19

15-051-00780-00-00

WELL LOG

Isern Drilling Company etal, Owner - Windholz #1
SW/4 SW/4 NW/4 Section 8, Township 12, Range 16W,
Ellis County, Kansas

ELEVATION: 1893 DF (Est) Figures indicate bottom of formation
0 to 60 post rock

PIPE RECORD:

8-5/8" set at 160'

TOPS: RBM

Topeka 2826 (-931)
Heebner 3075 (-1180)
Toronto 3096
Base Oread 3111
Lansing 3121 (-1226)
Base Kansas City 3360
Conglomerate 3408 (-1513)

360 shale & shells
375 sand & shale
430 shale & shells
515 sand & shale
600 shale & shells
750 sand & shale
850 shale & shells
1060 Red rock & shells
1100 Anhydrite
1500 shale & shells
1690 salt
1960 shale & shells
2220 lime & shale
2275 shale & shells
2535 lime & shale
2645 shale & shells
2690 lime & shale
2805 shale & shells
2984 lime & shale
2995 lime
3090 lime & shale
3408 lime
3475 Conglomerate
3476 Rotary TD D&A

Rotary Commenced 5-21-54
Completed 5-31-54

REC
STATE CORP

JUN 1 1954
6-3-1954
CONSERVATION DIVISION
Wichita, Kansas

STATE OF KANSAS)
COUNTY OF BARTON) ss

I, M. M. Shropshire, Drilling Superintendent of the above-described well, being first duly sworn on oath, declare: That I have knowledge of the facts, statements and matters herein contained pertaining to the log of the above-described well, as filed, and that the same are true and correct.

M. M. Shropshire

Subscribed and Sworn to before me this 1st day of June, 1954.

PLUGGING
FILE SEC 8 12 R 16W
BOOK PAGE 38 LINE 19

George Meyer
Notary Public

My commission expires Feb. 10, 1955.