


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Rooks County. Sec. 34 Twp. 10 Rge. 19W (E) (W)
Location as "NE/CNW/SW" or footage from lines SE NW SE
Lease Owner **Mallonee Drilling Company, Inc., etal**
Lease Name **Aksamit** Well No. **2**
Office Address **820 Union Center, Wichita, Kansas**
Character of Well (completed as Oil, Gas or Dry Hole) **Dry Hole**
Date well completed **9-18 1957**
Application for plugging filed **9-18 1957**
Application for plugging approved **9-18 1957**
Plugging commenced **9-18 1957**
Plugging completed **9-18 1957**
Reason for abandonment of well or producing formation **Non-producing**

If a producing well is abandoned, date of last production 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? **yes**

Name of Conservation Agent who supervised plugging of this well **Eldon Petty**
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well **3709** Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
		0	212'	8-5/8"	212'	None - cement circulated

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

**Plug set at 600', twenty sacks cement. Plug at 200', twenty sacks cement.
Plug at 40', ten sacks cement to top of hole. All plugs bridged with rock.**

12-6-57

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor **Mallonee Drilling Company, Inc.**
Address **820 Union Center, Wichita, Kansas**

STATE OF **KANSAS** COUNTY OF **SEDGWICK**, ss.
R. E. Mallonee (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) **R. E. Mallonee**
820 Union Center, Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this **23rd** day of **September**, 19 **57**

Notary Public.

My commission expires **December 14, 1957**

PLUGGING
FILED 34T. 10 R. 19W
BOOK PAGE 47 LINE 35

15-163-02524-000

DRILLERS' LOG
#2 Aksamit
SE NW SE Section 34-10-19W
Rooks County, Kansas

OPERATOR: Mallonee Drilling Company, Inc.
CONTRACTOR: Mallonee Drilling Company, Inc.

COMMENCED: September 3, 1957
COMPLETED: September 18, 1957
D & A

FROM	TO	DESCRIPTION
0	40	Post rock and shale
40	80	Shale and sand
80	105	Sand
105	212	Shale and shells
212	1190	Shale and shells
1190	1330	Shale and red bed
1330	1400	Shale and shells
1400	1440	Red bed and shale
1440	1470	Anhydrite
1470	1641	Shale and shells
1641	1652	Shale and iron
1652	1965	Shale
1965	1980	Lime and shale
1980	2045	Lime
2045	3008	Lime and shale
3008	3070	Shale
3070	3078	Lime
3078	3195	Lime and shale
3195	3245	Lime
3245	3335	Lime and shale
3335	3507	Lime
3507	3540	Lime and shale
3540	3620	Lime
3620	3630	Lime and shale
3630	3659	Cherty shale
3659	3709	Lime
3709		Rotary Total Depth

CASING RECORD
8-5/8" casing set at 212' with 130 sacks
Pozmix and one sack CC. Cement
circulated.

Drill Stem Test #1, 3365 - 77
Open 1 hour, rec. 545' salt water.
IBHP 927#, FBHP 874#

Drill Stem Test #2, 3378 - 98
Open 1 hour, rec. 10' mud.
IBHP 0#, FBHP 0#

Drill Stem Test #3, 3400 - 30
Open 1 hour, rec. 90' muddy water.
IBHP 1195#, FBHP 1025#

TOPS		
Elevation		2119 K.B.
Anhydrite	1440	/ 679
Topeka	3069	- 950
Toronto	3312	-1193
Lansing K.C.	3329	-1210
Base K.C.	3549	-1430
Conglomerate	3594	-1475
Arbuckle	3657	-1538
R.T.D.	3709	-1590

I hereby certify that to the best of my knowledge and belief, the above represents a true and accurate
Drillers' Log of the captioned well.

State of Kansas)
County of Sedgwick) ss

R. E. Mallonee
R. E. Mallonee

Subscribed and sworn to before me this 23rd day of September, 1957.

My commission expires:
December 14, 1957

Martha Gorges
Notary Public (Martha Gorges)