


STATE OF KANSAS
STATE CORPORATION COMMISSION
Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

WELL PLUGGING RECORD



Rooks County, Sec. 34 Twp. 10 Rge. 19 (E) (W)
Location as "NE/CNW/SW" or footage from lines C E/2 NW
Lease Owner Glacier Petroleum Company
Lease Name McKenna Well No. 1
Office Address 1009 Union Center Building Wichita, Kansas 67202
Character of Well (completed as Oil, Gas or Dry Hole) _____
Date well completed _____ 19____
Application for plugging filed 2-24-70 19____
Application for plugging approved 2-25-70 19____
Plugging commenced 3-6-70 19____
Plugging completed 3-12-70 19____
Reason for abandonment of well or producing formation _____

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Leo Massey
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3762 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS				CASING RECORD		
FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
		8 5/8		208	None	
		4 1/2		None	2531'.03	
				3761		
				RTCL		

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Dug out cellar after pulling unit laid out tubing and rods. Moved rig to location.
Set up pole. Pushed plug to 3300' with sand and dumped 4 sacks of cement. Rigged up jacks, had 17" tension.
Shot casing at 3200' and tried to pump down the casing. Shot casing at 3000' - 2800' - 2600' and 2525'. Pulled 30 joints of 4 1/2" casing.
Finished pulling 51 joints of casing. Loaded trailer and tallied pipe.
Tore down rig and moved off location. Halliburton squeezed well with 5 sacks of hulls, 40 sacks of mud and 120 sacks of 50/50 pozmix cement blended with 6% gel.

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Forbes Casing Pulling Company, Inc.
Address P. O. Box 221 Great Bend, Kansas 67530

STATE OF Kansas, COUNTY OF Barton, ss.
James W. Rockhold (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) James W. Rockhold
P. O. Box 221 Great Bend, Kansas (Address)
Subscribed and sworn to before me this 19 day of March 19 70
My commission expires May 1973
[Signature] Notary Public.



15-163-20221-0000

B & B DRILLING, INC.548 Petroleum Building
Wichita, Kansas 67202

July 7, 1969

RECEIVED
STATE CORPORATION COMMISSION
FEB 25 1970
CONSERVATION DIVISION
Wichita, KansasDRILLERS LOGRe: #1 McKenna
C E/2 NW Sec. 34-10S-19W
Rooks County, Kansas

COMPANY: Glacier Petroleum Co.
 CONTRACTOR: B & B Drilling, Inc.
 TOTAL DEPTH: 3762'
 COMMENCED: June 23, 1969
 COMPLETED: July 2, 1969

60	209	Sand & Shale
209	220	Shale
220	550	Shale
550	810	Sand
810	985	Shale
985	1240	Sand
1240	1330	Shale
1330	1507	Shale
1508	1540	Anhydrite
1540	1710	Shale
1710	2060	Shale & Red Bed
2060	2135	Shale W/Line Streaks.
2135	2440	Shale & Lime
2440	2527	Shale & Lime
2527	2783	Shale & Lime
2783	2977	Shale & Lime
2977	3140	Shale & Lime
3140	3257	Shale & Lime
3257	3392	Lime
3392	3448	Lime & Shale
3448	3460	Lime
3460	3490	Lime & Shale
3490	3525	Lime
3525	3595	Lime
3595	3647	Lime (Chert)
3647	3682	Lime & Chert
2682	3712	Lime & Chert
3712	3757	Lime
3757	3762	Lime
3762		Total Depth


DST # 1

DST # 2

Ran 3761' 4 1/2" casing w/ 50 sx Common & 2% Gel
 125 sx 50/50 Poz SS Plug @ 3738'

We certify the above and foregoing to be true and
 correct copy of the log on the #1 McKenna, located in
 Rooks County, Kansas.

Subscribed and sworn to before me this 7th day of July
 My commission expires May 31, 1970



Bill Lucas
 President
Alma A. Neiser