

15-163-01980-0001

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER Compl 8/44
LEASE NAME Casey

RECEIVED
STATE CORPORATION COMMISSION
7-6-98
JUL 16 1998

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

WELL NUMBER 1
2310
990 ETCC
4290 FT. from S Section Line
4290 FT. from E Section Line

LEASE OPERATOR Murfin Drilling Company, Inc.

SEC. 35 TWP. 10 RGE. 19 (X) of (6)

ADDRESS 250 N. Water, Suite 300, Wichita, KS 67202

COUNTY Rooks

PHONE# (785) 421-2103 OPERATORS LICENSE NO. 30606

Date Well Completed NA

Character of Well WSW Input
ETCC
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Commenced 6/30/98

Plugging Completed 6/30/98

The plugging proposal was approved on 6/30/98 (date)

by Dennis Hamel - Hays District (KCC District Agent's Name).

Is ACC-1 filed? _____ If not, is well log attached? _____

Producing Formation Dakota Depth to Top 677 Bottom 680 T.O. 883 3551

Show depth and thickness of all water, oil and gas formations. ETCC

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Dakota	water	677	680	<u>10-75</u> <u>8-5/8</u>	<u>98</u> <u>200'</u>	<u>0</u>
				<u>5 1/2</u>	<u>3495'</u>	<u>0</u>
				<u>4"</u>	<u>1601</u>	<u>0</u>

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from ___ feet to ___ feet each set.
Perforated 4" csg 850'. Ran tbg. to 871'. Pumped 30 sacks 150# hulls to circ to surface.
Pulled tbg. Squeezed 4" csg 4 more sacks 700# max pressure, 650# ISIP. Down 8 5/8" 30
sacks Midcon II, 100# hulls 300# max pressure 200# ISIP. Plugged at 11:30 A.M.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor _____ License No. _____


Address _____

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Murfin Drilling Company, Inc.

STATE OF Kansas COUNTY OF Graham, ss.

John Gerstner (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) John Gerstner
(Address) P.O. Box 130, Hill City, KS 67642



AND SWORN TO before me this 30th day of June, 19 98

Donna Gerstner
Notary Public

My Commission Expires: 6/24/2001