

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division,
State Corporation Commission,
800 Bittling Building,
Wichita, Kansas.

WELL PLUGGING RECORD

OR

FORMATION PLUGGING RECORD

Nov 8-37
1937

Strike out upper line
when reporting plugging
of formations.

NORTH

	35		

Locate well correctly on above
640 A. Plat

0790

Rooks County. Sec. 35 Twp. 10S Rge. 19 (E) 19 (W)

Lease Name John Casey
 Lease Owner Superior Oil Corporation
 Office Address 418 Exchange Bank Bldg, Tulsa, Oklahoma.
 Character of Well (Oil, Gas or Dry) Dry Total Depth of Well 3686'-8" Feet
 Date, well, completed 11-3-1937
 Application for plugging and log of well filed November 3 1937
 Application for plugging approved November 5 1937
 Plugging Commenced November 4 1937
 Plugging Completed November 5 1937
 Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 193
 Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Officer who supervised plugging of this well. Mr. Alexander, Great Bend, Kansas.

Producing formation _____ Depth to top _____ Bottom _____

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				12-1/2	148'8"	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Hole filled from bottom to 150' of the top with rotary mud pumped in with rotary pump, drove bridge through the 12-1/2 casing and put 15' of cement on top of the bridge, put another bridge 15' down below the bottom of the cellar and filled the hole with cement to the bottom of cellar.

35 10 19W
46 22

(If additional description is necessary use BACK of this sheet)

Does the above conform strictly to the Conservation Division regulations? Yes

Was exception made? No If so describe _____

Correspondence regarding this well should be addressed to W. R. Neely
Address Route 2,
Zurich, Kansas.

STATE OF Kansas COUNTY OF Paoli, ss.

W. R. Neely (employee of owner) or (owner or operator) of the above-described well, being first duly sworn deposes, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Superior Oil Corp. By W. R. Neely Supt
418 Exchange Bank Bldg. Tulsa, Okla
(Address)

SUBSCRIBED AND SWORN to before me this 6 day of Nov. 1937

My commission expires 11-27, 1937
W. L. Bartlett Notary Public.

FORMATION RECORD (Cont'd)

Description	Top	Bottom	Description	Top	Bottom
Coring lime	3362	3370			
Lime	3370	3403			
Cored lime	3403	3418			
Reamed core hole	3403	3418			
Lime	3418	3446			
Shale, red	3446	3455			
Lime	3455	3532			
Lime, with red & green shale breaks	3532	3548			
Top Conglomerate	3548	3551			
Lime & green shale	3548	3565			
Lime & Shale	3565	3567			
Cored lime shale	3567	3581			
" "	3581	3584			
Reamed to B1	3587	3604			
Lime, shale, chert	3584	3604			
Lime, chert	3604	3615			
Chert & shale	3615	3624			
Shale, red & green	3624	3640			
Bottom Conglomerate		3640			
Shale, red & green	3640	3651			
Top Siliceous	3651				
Cored "	3652-6	3653-6			
" "	3655-6	3656-6			
Cored Lime	3656-6	3663-6			
Reamed to B1	3652-6	3668-6			
Cored	3668-6	3677-6			
Cored Lime	3677-6	3686-6			
Total Depth		3686-2			

ERNEST E. BLINCOE, CHAIRMAN
HOMER HOCH
E. R. SLOAN
COMMISSIONERS

PHONES 2-0488—L. D. 78

E. G. DAHLGREN, DIRECTOR, WICHITA
MARVIN LEE, TECHNICAL ADVISER




LEO R. PRICE, SECRETARY
INNIS D. HARRIS, ATTORNEY

801 HARRISON
TOPEKA, KANSAS

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
800 BITTING BUILDING
WICHITA, KANSAS

IN REPLY PLEASE
REFER TO THIS
SUBJECT



November 8, 1937

W. R. Neely
Route 2

Zurich, Kansas

IN ACCOUNT WITH Conservation Division, State Corporation Commission

Wichita, Kansas

WE Charge YOU

Plugging Assessment..... \$25.00

Well No. 1
Farm Casey
Description 35-10-19W
County Rooks
File 116-22

The assessment for the plugging of all wells is one cent per foot, with a maximum of \$25.00 and a minimum of \$5.00.

This Assessment will be past due December 6, 1937.

TRJ:ha

PLEASE RETURN ONE COPY WITH REMITTANCE

PLUGGING
FILE SEC 35-T-10-R-19W
BOOK PAGE 116 LINE-22

pd \$25.00
12-2-37
bw

15-163-03862-0000

ERNEST E. BLINCOE, CHAIRMAN
HOMER HOCH
E. R. SLOAN
COMMISSIONERS

PHONES 2-0488—L. D. 78

E. G. DAHLGREN, DIRECTOR, WICHITA
MARVIN LEE, TECHNICAL ADVISER



LEO R. PRICE, SECRETARY
INNIS D. HARRIS, ATTORNEY

801 HARRISON
TOPEKA, KANSAS

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
800 BITTING BUILDING
WICHITA, KANSAS

IN REPLY PLEASE
REFER TO THIS
SUBJECT

November 8, 1937

J. D. Neely

Route 2

Murich, Kansas

IN ACCOUNT WITH Conservation Division, State Corporation Commission
Wichita, Kansas

WE Charge YOU

Plugging Assessment..... \$25.00

Well No. 1
Farm Jersey
Description 35-10-19.4
County Hooka
File 116-22

The assessment for the plugging of all wells is one cent per foot,
with a maximum of \$25.00 and a minimum of \$5.00.

This Assessment will be past due December 6, 1937.

TRJ:ha

PLEASE RETURN ONE COPY WITH REMITTANCE