

TYPE OR PRINT
NOTICE: Fill out completely and return
to Cons. Div. office within 30 days.

LEASE NAME Wilson B
WELL NUMBER # 7
330 Ft. from S/N Line of Section (circle one)
990 Ft. from E/W Line of Section (circle one)

LEASE OPERATOR Paul Bowman Oil Company
ADDRESS 801 Codell Road
CITY, STATE, ZIP Codell, Kansas 67663-8500
PHONE#(913) 434-2633 OPERATORS LICENSE NO. 31008
Character of Well OIL
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

SPOT LOCATION NE - NW - NE -
SEC. 1 TWP. 10 S. RGE 20W (E) or (W)
COUNTY Rooks
Date Well Completed 09/19/53
Date Plugging Commenced 8/15/95
Date Plugging Completed 2:30p 8/15/95

The plugging proposal was approved on August 2, 1995 (date)
by Dennis Hammel (KCC District Agent's Name)

Is ACO-1 filed? No If not, is well log attached? _____

Producing Formation(s) ARBUCKIE Depth to Top 3783 Bottom 3787 T.D. 3791

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS				CASING RECORD		
FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULL OUT

Described in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet each set.

RECEIVED
STATE CORPORATION COMMISSION

11-20-95
NOV 2 1995

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Allied Cementing Company
License No. unavailable
Address P. O. Box 31 Russell, Kansas 67665
NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Paul H. Bowman
STATE OF Kansas COUNTY OF Rooks, ss.

CONFIDENTIAL

Teresa M. Bowman (Employee of Operator or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Teresa M. Bowman

(Address) 801 Codell Rd. Codell, KS 67663-8500

SUBSCRIBED AND SWORN TO before me this 17th day of November, 19 95

Janette M. Wehrli
Notary Public

My Commission Expires:



Well Records and Logs

15-163-01999-0000

Wilson B. #7
NE-NE-NW
1-10-20
Rooks Co.
Commenced 9-4-53
Completed 9-14-53

Elevation: 2257 R.B.
8 5/8" casing set @ 221' w/150 sacks
5 1/2" casing set @ 3782' w/125 sacks
Centralizers set @ 3764-3733-8698-3665.

Summary of Formations

Heebner-----3450
Toronto-----3471
Lansing-----3489 (-1232)
Conglomerate-----3731
Simpson-----3755
Reworked Arbuckle----3778
Solid Arbuckle-----3781 (-1524)
Total Depth-----3787

CT T.D. 3791

Drill Stem Tests

1. 3780-87 open 1 hr. Recovered 1620' oil. B.H.S.I.P. 1080# in 15"
I F P O #. F.F.P. 610#.

Cable Tools

Sept. 20 Move in tools, rig up. Start swabbing mud.
Sept. 21 Swab mud. Drill float and cement. Drill shoe at 3782',
clean out to 3787'. Rotary T.D. Swab 11 bbl. oil per
hr. No water.
Sept. 22 Drill 3787' - 3791' - Swab 33 bbl. per hr. No water.
Bail and clean up hole. Tear down.

STATE CORPORATION COMMISSION

Temporary filed Sept. 23, 1953.

10-13-53 - State Draw Down 3007 BBL