

15-163-02356-0000

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER None

LEASE NAME WILSON B

WELL NUMBER 9

4290 Ft. from S Section Line

2970 Ft. from E Section Line

SEC. 1 TWP. 10 SRGE. 20 ~~KE~~ or (W)

COUNTY Rooks

Date Well Completed 7/9/55

Plugging Commenced 1/21/86

Plugging Completed 1/21/86

LEASE OPERATOR Kaiser-Francis Oil Company

ADDRESS P. O. Box 21468, Tulsa, OK 74121-1468

PHONE#(918) 494-0000 OPERATORS LICENSE NO. 6568

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? District 6, Hays, KS

Is ACO-1 filed? on old form if not, is well log attached? ---

Producing Formation Arbuckle Depth to Top 3779 Bottom 3806 T.D. 3806

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
Arbuckle	Oil	3779	3806	8-5/8	187	-0-
				5-1/2	3779	-0-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Spotted 1st plug @ 2500' w/100 SXS 60/40 poz + 1-3/4 SXS hulls. Spotted 2nd plug @ 1300' w/75 SXS 60/40 poz + 1-1/2 SXS hulls. Spotted 3rd plug @ 600' w/45 SXS 60/40 poz + 1-1/4 SXS hulls & circulated to surface. Pumped 15 SXS cement down annulus. JOB COMPLETE.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Kaiser-Francis Oil Company License No. 6568

Address P. O. Box 21468, Tulsa, OK 74121-1468

STATE OF Oklahoma COUNTY OF Tulsa, ss.

Charlotte Van Valkenburg (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well, as filed that the same are true and correct, so help me God.

(Signature) [Signature]

(Address) P. O. Box 21468, Tulsa, OK 74121-1468

SUBSCRIBED AND SWORN TO before me this 14th day of March, 1986

[Signature]  
STATE CORPORATION COMMISSION

My Commission Expires: 2/11/89

MAR 17 1986  
3-17-86  
CONSERVATION DIVISION  
Wichita, Kansas

Form CP-4  
Revised 08-84

**KANSAS GEOLOGICAL SOCIETY**  
 KANSAS WELL LOG BUREAU - KANSAS WELL SAMPLE BUREAU  
 KANSAS GEOLOGICAL SOCIETY BUILDING  
 508 EAST MURDOCK - WICHITA, KANSAS

15-163-02356-8000

COMPANY **Francis Oil & Gas, Inc. & Hornum Cos. Kaiser, Oil Producer**  
 FARM **Wilson B** NO. **9**

SEC. **1** T. **10S** R. **20W**  
 LOC. **S5 NE NW**

TOTAL DEPTH **3784**  
 COMM. **6/27/55** COMP. **7/7/55**  
 SHOT OR TREATED  
 CONTRACTOR **H-30, Inc.**  
 ISSUED

COUNTY **Rocky KANSAS**


CASING

20	10	
15	8	187'
12	6	
13	5	377'

ELEVATION **2248 K.B.**

PRODUCTION

FIGURES INDICATE BOTTOM OF FORMATIONS

Surface Clay, Sand & Shale	110
Shale	770
Sand	880
Shale with Iron Streaks	1075
Shale & Shells	1200
Sand	1395
Shale, Shells & Red Bed	1685
Anhydrite	1725
Shale, Shells & Red Bed	1910
Shale & Shells	2085
Shale, Shells & Salt	2230
Shale & Lime	2492
Lime	2526
Lime & Shale	2570
Lime & Chert	2606
Lime	2631
Lime & Shale	2675
Lime & Chert	2760
Shale & Lime	2784

**FORMATION TOPS**

NEEDLER 3114  
 TORONTO 2465  
 LAISING 3403  
 ANNUCKLE 3770


I hereby certify that this is a true and correct log of the above described well as shown by the drilling reports.

**H-30, INC.**

By *L.P. Lounding*

STATE OF KANSAS |  
 COUNTY OF SEDGWICK | 582

Subscribed and sworn to before me, a notary public, in and for said County and State this 12th day of July, 1955.



*L.P. Lounding*  
 Notary Public

STATE OF KANSAS - COMMISSION

MAR 17 1986

CONSERVATION DIVISION  
 Wichita, Kansas