

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

15-163-01995-0000

API NUMBER None

LEASE NAME Wilson B

WELL NUMBER 3

3630 Ft. from S Section Line

3630 Ft. from E Section Line

SEC. 1 TWP. 10S RGE. 20 (E) or (W)

COUNTY Rooks

Date Well Completed 10-1-52

Plugging Commenced 5-7-85

Plugging Completed 5-7-85

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR Kaiser-Francis Oil Company

ADDRESS P. O. Box 21468 Tulsa, OK 74121-1468

PHONE (918) 494-0000 OPERATORS LICENSE NO. 6568

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? District 6, Hays, Ks

Is ACO-1 filed? on old form if not, is well log attached? --

Producing Formation Arbuckle Depth to Top 3816 Bottom 3825 T.D. 3825

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
<u>Arbuckle</u>	<u>Oil</u>	<u>3816</u>	<u>25</u>	<u>8-5/8</u>	<u>200</u>	<u>-0-</u>
				<u>5-1/2</u>	<u>3817</u>	<u>-0-</u>

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Spotted 40 sx cmt plug from 3825'-3457'. Gel plug from 3457'-1012'. Spotted 110 sx cmt plug from 1012'-surf. Pumped 70 sxs cmt down csg annulus. Plugging complete.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Kaiser-Francis Oil Company License No. 6568

Address P. O. Box 21468 Tulsa, OK 74121-1468

STATE OF Oklahoma COUNTY OF Tulsa

Drew Tyler (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Drew Tyler

(Address) P. O. Box 21468 Tulsa, OK 74121-1468

SUBSCRIBED AND SWORN TO before me this 23rd day of May, 19 85

Donna M. Knapp  
Notary Public

My Commission Expires: 11-22-86

L O G

Company: Francis Oil & Gas Co., et al  
 Contractor: Woody Speer  
 Drilling Commenced: 9/16/52  
 Drilling Completed: 10/1/52

Farm: Wilson B #3  
 Location: NW SE NW/4 Sec. 1-10S-20W  
 Rooks County, Kansas  
 Casing Record: 8-5/8" casing at 200'  
 with 125 sacks cement.  
 5 1/2" casing at 3817' with  
 150 sacks cement.

(figures below indicate bottoms)

Shale, Sand & Shells	190
Surface Depth	200
Shale & Shells	805
Red Bed & Shale	920
Shale & Shells	1185
Sand & Shale	1420
Shale	1525
Red Bed & Sand	1615
Shale & Shells	1677
Anhydrite	1710
Shale & Shells	1980
Lime & Shale	2980
Lime	2990
Shale & Lime	3460
Lime - Hard	3510
Lime	3581
Lime - Hard	3615
Lime	3735
Lime & Conglomerate (Cherty)	3757
Chert & Lime	3816
Lime	3825
R.T.D.	3825

I hereby certify that this is a true and correct log of the above described well as shown by the drilling reports.

WOODY SPEER

By Mesle Britting

STATE OF KANSAS }  
 } ss:  
 COUNTY OF SEDGWICK }

Subscribed and sworn to before me, a notary public, in and for said County and State this 6th day of October, 1952.

Harold Walton  
 Notary Public

My Commission Expires: Sept. 17, 1955.