

LEASE NAME GRAHAM

TYPE OR PRINT  
 NOTICE: Fill out completely  
 and return to Cons. Div.  
 office within 30 days.

WELL NUMBER 4

3630 Ft. from S Section Line

2310 Ft. from E Section Line

SEC. 1 TWP. 10S RGE. 20 <sup>XX</sup> or (W)

LEASE OPERATOR TEX/CON Oil & Gas Company

COUNTY Rooks

ADDRESS 9401 Southwest Freeway, Houston, TX 77074

Date Well Completed 5-24-54

PHONE# (713) 272-5000 OPERATORS LICENSE NO. 30323

Plugging Commenced 8-12-91

Character of Well Oil

Plugging Completed 8-13-91

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on \_\_\_\_\_ (date)

by Dennis Hamel (KCC District Agent's Name).

Is ACO-1 filed? yes If not, is well log attached? \_\_\_\_\_

Producing Formation Arbuckle Depth to Top 3796' Bottom 3799' T.D. 3799'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

RECEIVED

Formation	Content	From	To	Size	Put in	Pulled out
Arbuckle	Oil	3796'	99'	8-5/8"	158'	0
				5-1/2"	3796'	0

STATE CORPORATION

9-27-91

SEP 23 1991

CONSERVATOR  
 WICHITA, K.

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. POOH w/tbg & RBP. Perf csg @ 1680' & @ 950'. RIH to 3021'. Mixed & spotted 80 sxs of 60/40 Poz mix. Returns @ surface. POOH to 1685' and circ. 240 sxs of same with returns @ surface. Tied into 5 1/2" csg @ surface and pumped 25 sxs of 60/40 poz mix. Tied onto surface casing and mixed and pumped 55 sxs cmt down annulus. Cut off csg below plow depth & welded on steel cap.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Halliburton Services License No. 5287

Address 1100 East 8th St., Hays, KS 67601

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: TEX/CON Oil & Gas Company

STATE OF Texas COUNTY OF Harris, ss.

Cynthia Arnold (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Cynthia Arnold

(Address) 9401 Southwest Freeway, Houston, TX

SUBSCRIBED AND SWORN TO before me this 18th day of Sept., 19 91

Dennis R. Morales  
 Notary Public

My Commission Expires: 8/30/92