

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-097-30146-00-00  
Spot: NWSE Sec/Twnshp/Rge: 10-30S-19W  
1980 feet from S Section Line, 1980 feet from E Section Line  
Lease Name: DUNN Well #: 1-10  
County: KIOWA Total Vertical Depth: 5170 feet

Operator License No.: 8061  
Op Name: OIL PRODUCERS INC. OF KANSAS  
Address: 1710 WATERFRONT PKWY  
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		5000		WITH 2 SX CMT
SURF	8.625	405		WITH 300 SX CMT
PROD	5.5	5156	2525	WITH 100 SX CMT

108.03

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 09/25/2009 9:40 AM  
Plug Co. License No.: 34091 Plug Co. Name: BLACKHAWK WELL SERVICE, LLC  
Proposal Rcvd. from: DAVID HAYES Company: OIL PRODUCERS INC. OF KANSAS Phone: (620) 546-4456

Proposed Plugging Method: SET CIBP @ 5000' & 2 SX CMT. LOAD HOLE WITH GEL WATER & PUMP 50 SX CMT @ 1200'. PLUG AT 420' WITH 50 SX CMT. PLUG AT 40-0' WITH 10 SX CMT.

Plugging Proposal Received By: STEVE DURRANT Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 06/25/2009 12:00 PM KCC Agent: ERIC MACLAREN

Actual Plugging Report:

SET CIBP @ 5000' WITH 2 SX CMT. 1ST PLUG AT 1191' WITH 30 SX GELLED WATER & 50 SX CMT. 2ND PLUG AT 424' WITH 50 SX CMT. 3RD PLUG AT 60' WITH 30 SX CMT. CMT CIRCULATED.

Perfs:

Top	Bot	Thru	Comments
5044	5084		

RECEIVED  
JUL 13 2009  
KCC WICHITA

Remarks: USED 60/40 POZMIX 4% GEL BY BASIC ENERGY SERVICES.

Plugged through: CSG

INVOICED  
DATE: 9/11/09  
INV NO: 2010060191

District: 01

Signed Eric MacLaren  
(TECHNICIAN)

RECEIVED  
JUL - 7 2009  
KCC DODGE CITY

*(Handwritten mark)*