

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-189-20656-00-02
Spot: W2E2SENE Sec/Twnshp/Rge: 35-34S-35W
3300 feet from S Section Line, 510 feet from E Section Line
Lease Name: KINNEY CHESTER SAND UNIT Well #: 701 W
County: STEVENS Total Vertical Depth: 6829 feet

Operator License No.: 5447
Op Name: OXY USA INC.
Address: 5 E GREENWAY PLZ PO BOX 27570
HOUSTON, TX 77227

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	1660		WITH 800 SX CMT
COND	20	20		2 YDS REDI MIX 221.94
PROD	5.5	6829	2801	WITH 200 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 06/22/2009 9:00 AM
Plug Co. License No.: 31151 Plug Co. Name: SARGENT AND HORTON PLUGGING, INC.
Proposal Rcvd. from: DON HORTON Company: SARGENT AND HORTON PLUGGIN Phone: (580) 854-6515

Proposed Plugging Method: 1ST PLUG 50 SX CMT THROUGH TBG BEFORE CUT-OFF. 2ND PDLUG 25 SX CMT (FISH). 3RD PLUG AT 1680' WITH GEL WATER & 50 SX CMT. 4TH PLUG AT 600' WITH 40 SX CMT. 5TH PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: ERIC MACLAREN Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 06/22/2009 2:30 PM KCC Agent: JACK MACLASKEY

Actual Plugging Report:

2 3/8" TBG STUCK IN HOLE. 1ST PLUG AT 6498' WITH 50 SX CMT. CUT OFF 2 3/8" @ 3101'. 2ND PLUG AT 3101' WITH 25 SX CMT. TOC @ 2850'. 3RD PLUG AT 1680' WITH 50 SX CMT. 4TH PLUG AT 600' WITH 40 SX CMT. 5TH PLUG AT 40' WITH 10 SX CMT.

Perfs:

Top	Bot	Thru	Comments
6498	6526		TOC @ 5772'

RECEIVED
JUL 13 2009
KCC WICHITA

Remarks: USED COMMON CEMENT BY SARGENTS.

Plugged through: TBG

District: 01

Signed Jack d MacLaskey
(TECHNICIAN)

RECEIVED
JUN 26 2009
KCC DODGE CITY