

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-187-20762-00-00
Spot: SENE Sec/Twnshp/Rge: 17-30S-39W
3300 feet from S Section Line, 660 feet from E Section Line
Lease Name: ELLIOT SPENCER Well #: 1-17
County: STANTON Total Vertical Depth: 5900 feet

Operator License No.: 32309
Op Name: PRESCO WESTERN LLC
Address: 5665 FLATIRON PKWY
BOULDER, CO 80301

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		5570		WITH 2 SX CMT
SURF	8.625	1800		WITH 750 SX CMT 191.75
PROD	5.5	5900	0	WITH 200 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 06/30/2009 1:00 PM
Plug Co. License No.: 34069 Plug Co. Name: BASIC ENERGY SERVICES, LP
Proposal Rcvd. from: STEVE RIDENOUR Company: PRESCO WESTERN Phone: (620) 655-3459

Proposed Plugging Method: CIBP @ +/- 5570' W/ 2 SKS CMT. PLUG # 2 @ +/- 2950' W/ 20 SKS CMT. PLUG # 3 @ +/- 1800' W/ 20 SKS CMT. PLUG # 4 @ +/- 600' W/ 50 SKS. PLUG # 5 DUMP CMT DOWN SURFACE CSG W/ 20 SKS @ SURFACE (INSIDE CSG).

Plugging Proposal Received By: KEN JEHLIK Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 06/30/2009 6:30 PM KCC Agent: JACK MACLASKEY

Actual Plugging Report:

CIBP @ 5570' WITH 2 SX CMT. 1ST PLUG AT 2966' WITH 20 SX CMT. 2ND PLUG AT 1820' WITH 50 SX CMT. 3RD PLUG AT 600' WITH 50 SX CMT. 4TH PLUG AT 60' WITH 20 SX CMT. PUMP 40 SX CMT DOWN ANNULAR. PRESSURE TO 300 PSI.

Perfs:

Top	Bot	Thru	Comments
5610	5628		MORROW

9-1-09
2010060196
RECEIVED
JUL 13 2009
KCC WICHITA

Remarks: USED 60/40 POZMIX 4% GEL BY BASIC ENERGY.

Plugged through: TBG

District: 01

RECEIVED
JUL -7 2009
KCC DODGE CITY

Signed

Jack MacLaskey
(TECHNICIAN)