

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-159-05945-00-00
Spot: S2NWSW Sec/Twnshp/Rge: 23-19S-10W
1650 feet from S Section Line, 660 feet from W Section Line
Lease Name: BERNSTORF B Well #: 1
County: RICE Total Vertical Depth: 3290 feet

Operator License No.: 4767
Op Name: RITCHIE EXPLORATION, INC.
Address: 8100 E 22ND ST N # 700 BOX 783188
WICHITA, KS 67278

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	13	239		200 SX
PROD	7	3279		125 SX <u>106.93</u>

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 07/07/2009 9:00 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Revd. from: MIKE KELSO Company: MIKE'S TESTING & SALVAGE INC Phone: (620) 938-2943

Proposed Plugging Method: SEE BELOW

Plugging Proposal Received By: DUANE KRUEGER Witness Type: PARTIAL
Date/Time Plugging Completed: 07/07/2009 1:15 PM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

MIRU, CK BOTTOM. PERFORATE AT 1200', 850' AND 290'. RUN TUBING TO 3160' AND PUMP 100 SX'S CEMENT WITH 300#'S COTTON HULLS. PULL TUBING TO 1200' AND PUMP 50 SX'S CEMENT. PULL TUBING TO 850' AND PUMP 50 SX'S CEMENT. PULL TUBING TO 290' AND CIRCULATE CEMENT TO SURFACE. SHUT OFF VALVE ON 7" AND TRIED TO CIRCULATE ON BACKSIDE. PULL TUBING OUT. CONNECTED ONTO 7" AND DID GET CIRCULATION ON BACKSIDE. USED 420 SX'S TOTAL.

Perfs:

Top	Bot	Thru	Comments
3156	3165	CSG	LKC
3117	3124	CSG	
3109	3115	CSG	
3095	3097	CSG	
3078	3082	CSG	
2972	2976	CSG	
2943	2947	CSG	

9-1-09
2010060198

KANSAS CORPORATION COMMISSION
JUL 16 2009
RECEIVED

Remarks: 60-40 POZ, 4% GEL. LOG TECH OF KS TICKET #5763. COPELAND TICKET C-35321.

Plugged through: TBG

District: 02

Signed

Virgil Clothier
(TECHNICIAN)