

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-173-19031-00-02
Spot: SWSWSE Sec/Twnshp/Rge: 2-25S-2E
336 feet from S Section Line, 2329 feet from E Section Line
Lease Name: EILERT Well #: 1-INP
County: SEDGWICK Total Vertical Depth: 2838 feet

Operator License No.: 5920
Op Name: BANDY, TERRY P. DBA TE-PE OIL & G
Address: PO BOX 522
CANTON, KS 67428

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	174		150 SX
PROD	4.5	2832		100 SX

92.24

Well Type: EOR UIC Docket No: E23960.1 Date/Time to Plug: 07/07/2009 3:00 PM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: DAVE BRADY Company: QUALITY WELL SERVICE Phone: (620) 727-6964

Proposed Plugging Method: SAND TO 50' ABOVE TOP PERFS AND CAP WITH 4 SXS CEMENT. CIRCULATE WITH CEMENT FROM 250' TO SURFACE.

Plugging Proposal Received By: B. J. HOPE Witness Type: NONE
Date/Time Plugging Completed: 07/07/2009 5:00 PM KCC Agent: GREG EVES

Actual Plugging Report:

SANDED TO 2700' AND CAPPED W/4 SXS CEMENT. RAN TUBING TO 250' INSIDE THE 4 1/2 AND PUMPED 45 SXS TO CIRCULATE TO SURFACE. THE BACKSIDE OF CASING HAD ALREADY BEEN CEMENTED TO SURFACE.

NOVED
9-1-09
2010060199

Perfs:

Top	Bot	Thru	Comments
2830	2836		
2817	2819		
2807	2812		

KANSAS CORPORATION COMMISSION
JUL 16 2009
RECEIVED

Remarks: QUALITY WELL SERVICE TICKET #2322 TOTAL = 45 SXS 60/40 POZ 4% GEL
Plugged through: TBG

District: 02

Signed Greg Eves
(TECHNICIAN)