

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

00-02

API Well Number: 15-051-05898-00-01
Spot: NWSWNW Sec/Twnshp/Rge: 26-11S-17W
3560 feet from S Section Line, 5041 feet from E Section Line
Lease Name: HALL B Well #: 3
County: ELLIS Total Vertical Depth: 3923 feet

Operator License No.: 5030
Op Name: VESS OIL CORPORATION
Address: 1700 WATERFRONT PKWY BLDG 500
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	10.75	1109	0	w/300 sxs cmt
COND	15.5	106	0	w/100 sxs cmt <u>127.50</u>
L1	5.5	3499	0	
PROD	7	3383	0	w/250 sxs cmt

Well Type: SWD UIC Docket No: D03010.0 Date/Time to Plug: 07/07/2009 10:00 AM
Plug Co. License No.: 32452 Plug Co. Name: SMOKY HILLS WELL SERVICE
Proposal Rcvd. from: JOEL STULL Company: VESS OIL CORPORATION Phone: (785) 885-8240

Proposed Plugging Method: Ordered 425 sxs 60/40 pozmix - 4% gel - 400# hulls - 14 sxs gel.
Perfed at 1160'. Bridge plug at 3571'. Packer cemented in at 2521'.
Fish stuck in the hole at 2519'.
Squeezed from 2445' - 2478' w/50 sxs; 2627' - 2658' w/250 sxs.

Plugging Proposal Received By: RICHARD WILLIAMS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 07/07/2009 2:00 PM KCC Agent: PAT BEDORE

Actual Plugging Report:

Ran tubing to 2515' - pumped 14 sxs gel spacer followed with 15 sxs 60/40 pozmix - 4% gel.
Pulled tubing to 1600' - pumped 210 sxs 60/40 pozmix - 4% gel with 200# hulls -
circulated to surface.
Pulled all tubing - pumped 200 sxs 60/40 pozmix - 4% gel with 150# hulls.
S.I.P. 200#.
Hooked to 10 3/4" surface pipe. Pressured to 500# immediately.

Perfs:

AVO 010
DATE 9-1-09
WV NO 2010060200

RECEIVED
JUL 13 2009
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY-TICKET 334923.

Plugged through: TBG

District: 04

Signed

Pat Bedore

(TECHNICIAN)

CM

CITIES SERVICE OIL CO

#B-3 HALL

26-11-17W
NW SW NW

Contr.

ELLIS County

E. 1927

Comm. 11-25-37

Comp. 12-20-37

IP

3000 BOPD

Tops	Depth	Datum
ANH	1108	
LANS	3078	
ARB	3382	
TD	3400	

Casing
15" 106
10" 1121
7" 3383
2900' OIH @ 3392

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS

