

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-039-21039-00-00
Spot: NESESWNE Sec/Twnshp/Rge: 29-3S-28W
2030 feet from N Section Line, 1580 feet from E Section Line
Lease Name: BROWN Well #: 29-1
County: DECATUR Total Vertical Depth: 4150 feet

Operator License No.: 33335
Op Name: IA OPERATING, INC.
Address: 9915 W 21ST ST, STE B
WICHITA, KS 67205

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	250	0	180 sx
T1	2.875	3747		
PKR		3747		
PROD	5.5	3980	0	125 sx

134.88

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 07/21/2009 9:30 AM
Plug Co. License No.: 99998 Plug Co. Name: COMPANY TOOLS
Proposal Rcvd. from: MIKE STANTON Company: IA OPERATING, INC. Phone: (785) 483-9633

Proposed Plugging Method: Ordered out 380 sxs 60/40 pozmix - 4% gel - 300# hulls.
PC at 2438' w/265 sxs cwc.
Production Perfs: 3752' - 3754'.
Squeezed old production perfs: 3787'-3790'; 3777'-3780'; 3738'-3743' w/150 sxs.

Plugging Proposal Received By: RICHARD WILLIAMS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 07/21/2009 12:30 PM KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

S.O.S. Cementing pumped 75 sxs 60/40 pozmix - 4% gel with 300# hulls, followed with 275 sxs neat.
Max. P.S.I. 400#. S.I.P. 300#.
Hooked up to backside and pumped 5 sxs cement.
Max. P.S.I. 300#. S.I.P. 300#.

Perfs:

Top	Bot	Thru	Comments
3787	3790		
3777	3780		
3752	3754		
3739	3743		

9/14/09
2010060210
KANSAS CORPORATION COMMISSION
JUL 27 2009
RECEIVED

Remarks: S.O.S. CEMENTING COMPANY-TICKET #367.

Plugged through: CSG

District: 04

Signed Richard Williams
(TECHNICIAN) CM

PKJ

IA OPERATING
WICHITA KS 67205

#29-1 BROWN

29-03S-28W
2030'FNL & 1580'FEL, SEC
KANSAS

City: DECATUR
Site: 3-1/2 S & 2-1/4 E OF OBERLIN KS
Field: DECATUR CENTER SW

Spot: NE SE SW NE API 15-039-21039
Lat/Long: 39.76473 -100.48447

OIL

FR: 01/02/2008 Spd: 01/16/2008 Drlg Cp: 01/23/2008 Issued: 05/26/2008 Revised: 05/26/2008

Copyright 2008 Independent Oil & Gas Service, Inc. Wichita, KS

Side 1

IP Status:

OIL, P 10 BOPD, LKC, INTV NA, 4/5/2008

Contr: MURFIN DRILLING #3

Elev: 2700 EGL

Formation Tops: (L-Log, S-Sample, D-Driller)

NO TOPS RPTD

ERTD

4150 -1450

Csg: 8-5/8" 250+ (ALT 1), PROD CSG NA

Finds:

COMMENT: PROPOSED START 1/8/2008; MI &

RURT 1/16/2008

NO CORES

DSTS TAKEN - DETAILS NA

Comp Info: TRGT ZN: LKC (OIL), PTD 4150 (LKC),

MICT - CO, PF (LKC) INTV NA, ACD, SWB LD, GSO,

POP, P 10 BOPD, 4/5/2008 - TIGHT HOLE - NO

OTHER INFO AVAILABLE - TEMP COMP 5/26/2008