

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-167-23580-00-00  
Spot: NWNESENW Sec/Twnshp/Rge: 14-13S-15W  
1330 feet from N Section Line, 2270 feet from W Section Line  
Lease Name: BRUNGARDT Well #: 1  
County: RUSSELL Total Vertical Depth: 3340 feet

Operator License No.: 34259  
Op Name: JAG OPERATIONS, INC.  
Address: 710 S. FRONT PO BOX 628  
RUSSELL, KS 67665

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	254		

108.55

Well Type: DH UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 07/27/2009 8:00 AM  
Plug Co. License No.: 33350 Plug Co. Name: SOUTHWIND DRILLING, INC.  
Proposal Rcvd. from: LOU Company: JAG OPERATIONS, INC. Phone: (785) 445-4142

Proposed Plugging Method: Ordered 230 sxs 60/40 pozmix - 4% gel with 1/4# flocele per sack.  
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: CASE MORRIS WitnessType: NONE  
Date/Time Plugging Completed: 07/27/2009 10:30 AM KCC Agent: CASE MORRIS

Actual Plugging Report:

Perfs:

1st. Plug at 3293' w/25 sxs.  
2nd. Plug at 989' w/25 sxs.  
3rd. Plug at 507' w/100 sxs.  
4th. Plug at 304' w/40 sxs.  
5th. Plug at 40' w/10 sxs.  
Rathole with 30 sxs.

RECEIVED  
AUG 04 2009  
KCC WICHITA

9/4/09  
2010060211

Remarks: QUALITY OILWELL CEMENTING COMPANY.

Plugged through: DP

District: 04

Signed \_\_\_\_\_  
(TECHNICIAN)

Handwritten initials