

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-009-21099-00-00  
Spot: NWNWSE Sec/Twnshp/Rge: 26-16S-12W  
2390 feet from S Section Line, 2440 feet from E Section Line  
Lease Name: HARZMAN Well #: 2  
County: BARTON Total Vertical Depth: 3723 feet

Operator License No.: 9951  
Op Name: KRIER, KIRBY OIL, INC.  
Address: 1043 NE 80TH RD  
CLAFLIN, KS 67525

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	9.625	843		
PROD 7		3496		

121.00

Well Type: SWD UIC Docket No: D18673.0 Date/Time to Plug: 07/24/2009 9:00 AM  
Plug Co. License No.: 32098 Plug Co. Name: CLASSIC WELL SERVICE, INC.  
Proposal Rcvd. from: KIRBY KRIER Company: KRIER, KIRBY OIL, INC. Phone: (620) 587-3810

Proposed Plugging Method: Ordered 450 sxs 60/40 pozmix - 4% gel - 500# hulls - 20 sxs gel.  
Junk in the well at 3400' - worked for 21 days to clean out hole.

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 07/24/2009 2:00 PM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Perfed at 1550' and 650'.  
Ran tubing to 3368' - tied to tubing - pumped 20 sxs gel - 75 sxs cement with 100# hulls.  
Pulled to 2100' - pumped 200 sxs cement with 200# hulls.  
Pulled to 1100' - pumped 100 sxs cement with 200# hulls - circulated cement to surface.  
Pulled tubing - tied to casing - pumped 70 sxs.  
Shut in 250# P.S.I. - circulated out backside.  
Tied to backside and pumped 5 sxs.  
Max. P.S.I. 50#.

Perfs:

RECEIVED  
AUG 04 2009  
KCC WICHITA

9/4/09  
2010060213

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: CSG

District: 04

Signed Bruce Rodie  
(TECHNICIAN) CM

Form CP-2/3

JUL 30 2009

PS

GULF OIL CORP. 26-16-12  
 P.O. BOX 12116 #2 HAZMAN 195' FNL  
 CRDA. CITY, OK. 195' FWL, SE  
 CONTR STEF. INC. DRUG. CO. CITY BARTON  
 GEOL H. O. ARNOLD FIELD KRAFT-PRUSA

E 1935 LB CM 11/14/76 <sup>CARD</sup> ISSUED 2/17/77 IP SWDW  
 REAGAN SD 3496-3723

+	+	-
+	+	-

API 15-009-21,099

LOG	TOPS	DEPTH	DATUM
TOP	2722	- 787	
HEEB	3012	-1077	
TQR	3024	-1089	
DOUC	3039	-1104	
LANS	3119	-1184	
EKC	3351	-1416	
CONG	3379	-1444	
ARB	3424	-1489	
RTD	3497	-1562	
LTD	3502	-1567	
*REAGAN SD	3600	-1665	
DDTD	3723	-1788	
*SMP TOP			

9-5/8" 343/500sx, 7" 3496/450sx  
 NO DST'S  
 MICT - CO, AC 2000, SWB LD, SWDW

INDEPENDENT OIL & GAS SERVICE  
 WICHITA, KANSAS