

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-185-22453-00-01
Spot: SWNWNE Sec/Twnshp/Rge: 27-24S-14W
4190 feet from S Section Line, 2310 feet from E Section Line
Lease Name: KEYSER REEVES OWO Well #: 1
County: STAFFORD Total Vertical Depth: 4270 feet

Operator License No.: 8061
Op Name: OIL PRODUCERS INC. OF KANSAS
Address: 1710 WATERFRONT PKWY
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		3744		
CIBP		4225		
SURF	8.625	255		WITH 170 SX CMT
PROD	5.5	4267	1015	WITH 175 SX CMT

138.78

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 07/06/2009 11:00 AM
Plug Co. License No.: 34069 Plug Co. Name: BASIC ENERGY SERVICES, LP
Proposal Rcvd. from: BARRY WALTERS Company: BLACKHAWK WELL SERVICE Phone: _____

Proposed Plugging Method: PLUGGING PROPOSAL SAME AS ACTUAL PLUGGING.

Plugging Proposal Received By: STEVE DURRANT Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 07/06/2009 12:50 PM KCC Agent: RICHARD LACEY

Actual Plugging Report:

RAN TBG TO 3740' & SPOTTED 55 SX CMT. PULLED TBG TO 960' & PUMPED 10 SX GEL. SPOTTED TOP PLUGS THROUGH CASING. 1ST PLUG AT 932' WITH 50 SX CMT. 2ND PLUG AT 276' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 20 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4202	4204		ARBUCKLE
3784	3788		LANSING KC "H"

KANSAS CORPORATION COMMISSION

JUL 31 2009

RECEIVED

Remarks: USED 60/40 POZMIX 4% GEL BY BASIC ENERGY.

Plugged through:

District: 01

RECEIVED

JUL 14 2009

KCC DODGE CITY

Signed

Richard W. Lacey

(TECHNICIAN)