

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-187-20971-00-00
Spot: SESESW Sec/Twnshp/Rge: 33-28S-40W
442 feet from S Section Line, 2299 feet from W Section Line
Lease Name: WESTERN FEED YARD Well #: 2-1433
County: STANTON Total Vertical Depth: 5509 feet

Operator License No.: 32309
Op Name: PRESCO WESTERN LLC
Address: 5665 FLATIRON PKWY
BOULDER, CO 80301

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		5370		WITH 2 SX CMT
SURF	8.625	1727		WITH 725 SX CMT
DVT		3076		
PROD	5.5	5509	0	WITH 275 SX CMT

179.04

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 07/07/2009 9:30 AM
Plug Co. License No.: 34069 Plug Co. Name: BASIC ENERGY SERVICES, LP
Proposal Rcvd. from: STEVE RIDENOUR Company: PRESCO WESTERN Phone: (620) 655-3459

Proposed Plugging Method: PLUGGING PROPOSAL SAME AS ACTUAL PLUGGING.

Plugging Proposal Received By: _____ Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 07/07/2009 3:00 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

1ST PLUG SET CIBP @ 5370' & 2 SX CMT. 2ND PLUG RAN BOND LOG TO EST. TOC @ 1965'. PERFORATE @ 1750'. PUMPED CMT & CIRCULATED TO SURFACE USING 400 SX CMT.

Perfs:

Top	Bot	Thru	Comments
5415	5429		MORROW

KANSAS CORPORATION COMMISSION

JUL 31 2009

RECEIVED

Remarks: USED 60/40 POZMIX 4% GEL BY BASIC ENERGY.

Plugged through: CSG

District: 01

RECEIVED

JUL 20 2009

KCC DODGE CITY

Signed

Ken Jehlik

(TECHNICIAN)

Form CR-20