

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-009-20496-00-00  
Spot: NWSESW Sec/Twnshp/Rge: 11-19S-15W  
990 feet from S Section Line, 3630 feet from E Section Line  
Lease Name: PASCOE A Well #: 3  
County: BARTON Total Vertical Depth: 3580 feet

Operator License No.: 5617  
Op Name: THE PYRAMID CORPORATION, INC.  
Address: 1030 VINCENT ST  
WICHITA, KS 67206

| String | Size  | Depth (ft) | Pulled (ft) | Comment              |
|--------|-------|------------|-------------|----------------------|
| SURF   | 8.625 | 916        | 0           | 170 SX               |
| PROD   | 5.5   | 3567       | 1820        | 150 SX <u>116.35</u> |

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 07/10/2009 9:00 AM  
Plug Co. License No.: 31528 Plug Co. Name: KELSO, MIKE OIL, INC.  
Proposal Rcvd. from: MIKE KELSO Company: THE PYRAMID CORPORATION, IN Phone: (620) 938-2943

Proposed Plugging Method: Ordered 350 sxs 60/40 pozmix - 4% gel - 500# hulls.

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 07/10/2009 1:00 PM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Sanded off bottom and topped with 5 sxs cement.  
Cut casing 1820' - pulled to 1500' - tied to casing and pumped 150 sxs cement with 200# hulls.  
Pulled casing to 900' - pumped 40 sxs cement with 150# hulls.  
Pulled casing to 300' - pumped 120 sxs cement with 100# hulls - circulated cement to surface.  
Pulled casing - hole stayed full.

Perfs:

| Top  | Bot  | Thru | Comments |
|------|------|------|----------|
| 3559 | 3572 |      |          |

9/4/09  
2010060223  
RECEIVED  
JUL 20 2009  
KCC WICHITA

Remarks: COPELAND ACID AND CEMENTING COMPANY-TICKET#C33025.

Plugged through: CSG

District: 04

Signed Bruce Rodie  
(TECHNICIAN)

CM


Form CP-2/3

JUL 15 2009

PKT

PYRAMID CORPORATION, INC. #3 PASCO "A" 11-19-15W  
 WICHITA, KANSAS NW SE SW  
 CONTR DUKE DRILLING CTY BARTON  
 GEOL CARL TODD FIELD OTIS-ALBERT

E 1949 KB CM 4/16/70 <sup>CARD</sup> ISSUED 7/16/70 IP P 40 BO + 40 BW  
 REAGAN 3566 1/2 -80



API 15-009-20,496

| SMP    | TOPS | DEPTH | DATUM |
|--------|------|-------|-------|
| ANHY   |      | 895   | +1054 |
| B ANHY |      | 925   | +1024 |
| HEEB   |      | 3162  | -1213 |
| DOUG   |      | 3191  | -1242 |
| BN L   |      | 3240  | -1291 |
| LANS   |      | 3250  | -1301 |
| REAGAN |      | 3563  | -1614 |
| TD     |      | 3580  | -1631 |

8 5/8" 916/400SX; 5 1/2" 3566 1/2 /150SX  
 DST(1) 3401-3422/30-45-60-45, REC 80'  
 THIN M, BHP 757-788#/45", FP 42-32#  
 DST(2) 3566-80/30-45-60-45, REC 90' GSY  
 MC OIL, 60' OCM & W, 90' OCMW, BHP  
 860-840#, FP 53-116#  
 CO TD BAIL 20GALS MDY OIL 13 GALS MW PH  
 150' M OIL & 150' MW, 6/3569-72(O.H) FU  
 250' OIL 200 WTR SWB DN 250 GALS MCA SWB  
 DN FU 200' M OIL, 400' WTR SWB 13GALS OIL  
 37 GALS WPH FU 21BF/36HRS FRAC 1500#SD  
 SWB PT LD & SWB 5BFLPH 70% OIL SWB LD &  
 SWB 8 1/2 BO & 6 3/4 BW PER HR, POP

NO LOG

INDEPENDENT OIL & GAS SERVICE  
 WICHITA, KANSAS