

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-127-20135-00-00  
Spot: SWNESW Sec/Twnshp/Rge: 11-16S-7E  
1320 feet from S Section Line, 3860 feet from E Section Line  
Lease Name: LEEDS Well #: 1-11  
County: MORRIS Total Vertical Depth: 1487 feet

Operator License No.: 5817  
Op Name: BENSON MINERAL GROUP, INC.  
Address: 1560 BROADWAY STE 1900  
DENVER, CO 80202

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	7	50		168 SX
PROD	2.875	1487		CEMENT CIRCULATED TO SURF

48.33

Well Type: GAS UIC Docket No: 5721 Date/Time to Plug: 07/09/2009 10:00 AM  
Plug Co. License No.: 33961 Plug Co. Name: Glacier Petroleum Co Inc CONSOLIDATED OIL WELL SERVICES LLC  
Proposal Rcvd. from: JEFF HAWES Company: GLACIER PETROLEUM Phone: (785) 366-6649

Proposed Plugging Method: RUN DOWN BACKSIDE WITH 1" TO 150' AND CIRCULATE TO SURFACE. THEN PUMP TUBING FULL TO SURFACE.

Plugging Proposal Received By: GREG EVES  
Date/Time Plugging Completed: 07/09/2009 3:00 PM

Witness Type: COMPLETE (100%)  
KCC Agent: GREG EVES

Actual Plugging Report:

BACKSIDE OF 2 7/8" TUBING WAS CEMENTED TO SURFACE. LOADED 2 7/8" AND THEN PUMPED WATER TO CONFIRM FORMATION WAS TAKING FLUIDS. PUMPED 65 SXS THROUGH 2 7/8" TO FILL TO SURFACE. (1 SACK COTTONSEED HULLS WAS MIXED IN AT BEGINNING OF CEMENT TO PLUG PERFORATIONS)

Perfs:

Top	Bot	Thru	Comments
1460	1470		

INVOICED  
DATE: 8-31-09  
INV. NO. 2010060165

KANSAS CORPORATION COMMISSION  
JUL 28 2009  
RECEIVED

Remarks: CONSOLIDATED WELL SERVICE TICKET #23406 TOTAL = 65 SXS 60/40 POZ 4% GEL

Plugged through: TBG

District: 02

Signed Greg Eves  
(TECHNICIAN)