

KANSAS CORPORATION COMMISSION
 OIL & GAS CONSERVATION DIVISION
WELL PLUGGING APPLICATION
 Please TYPE Form and File ONE Copy

Form CP-1
 March 2009
This Form must be Typed
Form must be Signed
All blanks must be Filled

OPERATOR: License #: 7030
 Name: John Roy Evans Oil Company, LLC
 Address 1: P.O. Box 385
 Address 2: _____
 City: Clafin State: KS Zip: 67525 + 0385
 Contact Person: Gary Kirmer
 Phone: (620) 793-2026

API No. 15 - 053-20712 - 0000
 If pre 1967, supply original completion date: _____
 Spot Description: _____
- NE NE SW Sec. 30 Twp. 17 S. R. 10 East West
2,310 Feet from North / South Line of Section
2,310 Feet from East / West Line of Section
 Footages Calculated from Nearest Outside Section Corner:
 NE NW SE SW
 County: Ellsworth
 Lease Name: Beck Well #: 5

RECEIVED
AUG 21 2009

KCC WICHITA

Check One: Oil Well Gas Well OG D&A Cathodic Water Supply Well Other: _____
 SWD Permit #: _____ ENHR Permit #: _____ Gas Storage Permit #: _____

Conductor Casing Size: _____ Set at: _____ Cemented with: _____ Sacks
 Surface Casing Size: 8 5/8" Set at: 261' Cemented with: 200 Sacks
 Production Casing Size: 4 1/2" Set at: 3310' Cemented with: 150 Sacks

List (ALL) Perforations and Bridge Plug Sets:
3272-3276, 4 shots per ft.

Elevation: 1817' (G.L. / K.B.) T.D.: 3310' PBTD: 3310' Anhydrite Depth: 653'
(Stone Corral Formation)

Condition of Well: Good Poor Junk in Hole Casing Leak at: 2000' to 2350'
(Interval)

Proposed Method of Plugging (attach a separate page if additional space is needed):

Bottom perms were sanded of to 2985'. Csg leak was squeezed with 325 sx common cement, Got out of hole when drlg cement @ 2440'. Perforate 2 shots/ft @ 1300', 950' and 311'. Ran tubing to 2400' and pump 50 sx plug @ 1300'. 35 sx plug @ 950'. Pull tubing to 311' and circulate cement to surface.

Is Well Log attached to this application? Yes No Is ACO-1 filed? Yes No

If ACO-1 not filed, explain why:

Plugging of this Well will be done in accordance with K.S.A. 55-101 et. seq. and the Rules and Regulations of the State Corporation Commission

Company Representative authorized to supervise plugging operations: Gary Kirmer
 Address: P.O. Box 385 City: Clafin State: KS Zip: 67525 + 0385
 Phone: (620) 793-2026
 Plugging Contractor License #: 3004 Name: Gressel Oilfield Service Inc.
Copoland Acid & Cement
 Address 1: P.O. Box 438 Address 2: _____
 City: Haysville State: KS Zip: 67060 + 0438
 Phone: (316) 524-1225

Proposed Date of Plugging (if known): 8-13-09

Payment of the Plugging Fee (K.A.R. 82-3-118) will be guaranteed by Operator or Agent

Date: 8-14-09 Authorized Operator / Agent: [Signature]
(Signature)

Dist 2
PKT

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

~~KCC~~ KCC - Well Plugged - PKT