

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING APPLICATION
Please TYPE Form and File ONE Copy

Form CP-1
March 2009
This Form must be Typed
Form must be Signed
All blanks must be Filled

OPERATOR: License #: 5056
Name: F.G. Holl Company, L.L.C.
Address 1: 9431 E. Central, Suite 100
Address 2: _____
City: Wichita State: KS Zip: 67206 + _____
Contact Person: Franklin R. Greenbaum
Phone: (316) 684-8481, Ext. 206

API No. 15 - 047-20,924-0000
If pre 1967, supply original completion date: _____
Spot Description: _____
~~SE~~ ^{SW} NE NE NW Sec. 13 Twp. 24 S. R. 17 East West
440 Feet from North South Line of Section
440 3080 Feet from East West Line of Section
Footages Calculated from Nearest Outside Section Corner:
 NE NW SE SW
County: Edwards
Lease Name: HAWLEY Well #: 4-13

Check One: Oil Well Gas Well OG D&A Cathodic Water Supply Well Other: _____
 SWD Permit #: _____ ENHR Permit #: _____ Gas Storage Permit #: _____
Conductor Casing Size: _____ Set at: _____ Cemented with: _____ Sacks
Surface Casing Size: 8-5/8" Set at: 274' Cemented with: 225sx Sacks
Production Casing Size: 4-1/2" Set at: 4371' Cemented with: 225sx Sacks

List (ALL) Perforations and Bridge Plug Sets:

Elevation: 2107 (G.L. / K.B.) T.D.: 4375' PBD: 4325' Anhydrite Depth: 1088'
(Stone Corral Formation)

Condition of Well: Good Poor Junk in Hole Casing Leak at: _____
(Interval)

Proposed Method of Plugging (attach a separate page if additional space is needed):

Heavy mud, hulls, cement and plug according to KCC specifications

Is Well Log attached to this application? Yes No Is ACO-1 filed? Yes No

If ACO-1 not filed, explain why:

RECEIVED
AUG 25 2009
KCC WICHITA

Plugging of this Well will be done in accordance with K.S.A. 55-101 et. seq. and the Rules and Regulations of the State Corporation Commission

Company Representative authorized to supervise plugging operations: Mr. Rob Long
Address: 701 E. Santa Fe, Box 308 City: Ellinwood State: KS Zip: 67526 + _____
Phone: (620) 793-0915
Plugging Contractor License #: 31925 Name: Quality Well Service
Address 1: 190 US Highway 56 Address 2: _____
City: Ellinwood State: KS Zip: 67526 + _____
Phone: (620) 727-3410

Proposed Date of Plugging (if known): Not known

Payment of the Plugging Fee (K.A.R. 82-3-118) will be guaranteed by Operator or Agent

Date: 8/21/2009 Authorized Operator / Agent: Loveness Manje
(Signature)

Dist #1
PK

STERLING DRILLING COMPANY
 P. O. Box 129
 Sterling, Kansas 67579

WELL LOG ***** HAWLEY #4-13
 Located: 440' RNE, 440' FEL, NW/4, Section 13-24S-17W,
 Edwards County, Kansas

OWNER: P. G. Holt
 ROTARY DRILLING CONTRACTOR: Sterling Drilling Company

COMMENCED: August 23, 1981
 COMPLETED: August 29, 1981

TOTAL DEPTH: 4375'

<u>LOG</u>	
0 = 93	Sand
93 = 277	Clay and Shale
277 = 1088	Red Beds, Sand and Shale
1088 = 1102	Anhydrite
1102 = 1277	Shales
1277 = 4375	Lime and Shale

CASING RECORD

Ran 7 joints new 8 5/8", 24# casing.
 262.47' pipe set at 277' K.B.
 Cemented with 225 sacks 60/40 Pozmix
 with 3/4 cc. Plug down at 4:00 PM,
 8-23-81, by Howco.

Ran 119 joints used 4 1/2", 10.5#
 casing. 4361.91' pipe set at 1277'
 K.B. Cemented with 100 sacks Lite
 and 125 sacks 50/50 Pozmix, plus
 regular additives. Plug down at 4:45
 PM, 8-29-81, by Howco.

RECEIVED
 AUG 25 2009
 KCC WICHITA

Deviation Surveys: 3/4" at 2177'
 Deviation Surveys: 2" at 4300'
 2" at 4300'



CORPORATION COMMISSION

Mark Parkinson, Governor Thomas E. Wright, Chairman Michael C. Moffet, Commissioner Joseph F. Harkins, Commissioner

NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)

HOLL, F.G., COMPANY L.L.C.
9431 E CENTRAL STE 100
WICHITA, KS 67206-2563

September 02, 2009

Re: HAWLEY #4-13
API 15-047-20924-00-00
13-24S-17W, 4840 FSL 3080 FEL
EDWARDS COUNTY, KANSAS

Dear Operator:

This letter is to notify you that the Conservation Division has received your plugging proposal, form CP-1, for the above well and has reviewed the proposal for completeness. The central office will now forward your CP-1 to the district office listed below for review of the proposed plugging method. **Please contact the district office for approval of your proposed plugging method at least five (5) days before plugging the well, pursuant to K.A.R. 82-3-113(b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit in accordance with K.A.R. 82-3-600.**

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well. This notice in no way constitutes authorization to plug the above well by persons not having legal rights of ownership or interest in the well.

This notice is void after March 1, 2010. The CP-1 filing does not bring the above well into compliance with K.A.R. 82-3-111 with regard to the Commission's temporary abandonment requirements.

Sincerely,

Steve Bond
Production Department Supervisor

District: #1
210 E Frontview, Suite A
Dodge City, KS 67801
(620) 225-8888