

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING APPLICATION
Please TYPE Form and File ONE Copy

Form CP-1
March 2009
This Form must be Typed
Form must be Signed
All blanks must be Filled

OPERATOR: License #: 30762
Name: Oil Company of America, Inc.
Address 1: 1200 Main St. Suite # 101
Address 2: _____
City: Hays State: KS Zip: 67601 + _____
Contact Person: Darrel Herl
Phone: (785) 628-3800

API No. 15 - 051-03202 - 0000
If pre 1967, supply original completion date: March 8, 1957
Spot Description: NW/4
-NW SW/NW Sec. 13 Twp. 15 S. R. 18 East West
3,630 Feet from North / South Line of Section
4,950 Feet from East / West Line of Section
Footages Calculated from Nearest Outside Section Corner:
 NE NW SE SW
County: Ellis
Lease Name: TS Leiker Well #: 12

Check One: Oil Well Gas Well OG D&A Cathodic Water Supply Well Other: _____
 SWD Permit #: _____ ENHR Permit #: _____ Gas Storage Permit #: _____

Conductor Casing Size: _____ Set at: _____ Cemented with: _____ Sacks
Surface Casing Size: 8 5/8" Set at: 1174' Cemented with: 550 Sacks
Production Casing Size: 5 1/2" Set at: 3619' Cemented with: 150 Sacks

List (ALL) Perforations and Bridge Plug Sets:

Open-hole Arbuckle, no perforations. No bridge plugs.

Elevation: 2017' (G.L. / K.B.) T.D.: 3619 PBDT: N/A Anhydrite Depth: 1162'
(Stone Corral Formation)

Condition of Well: Good Poor Junk in Hole Casing Leak at: _____
(Interval)

Proposed Method of Plugging (attach a separate page if additional space is needed):

Sand off bottom to 50' above open-hole and cement w/5 sxs with dump bailer. Shoot pipe @ 2000' (or deeper). Pull to 1750' and spot 150 sxs cement and 300 hulls. Pull to 1175' and spot 40 sxs and 100 hulls. Pull to 550' and spot 40 sxs. Pull to 150' and circulate with 40 sxs.

Is Well Log attached to this application? Yes No Is ACO-1 filed? Yes No

If ACO-1 not filed, explain why:

KANSAS CORPORATION COMMISSION

AUG 26 2009

RECEIVED

Plugging of this Well will be done in accordance with K.S.A. 55-101 et. seq. and the Rules and Regulations of the State Corporation Commission

Company Representative authorized to supervise plugging operations: Darrel Herl

Address: 1200 Main St. Suite #101 City: Hays State: KS Zip: 67601 + _____

Phone: (785) 628-3800

Plugging Contractor License #: 32810 Name: Professional Pulling Services, LLC

Address 1: PO Box 486 Address 2: _____

City: Hays State: KS Zip: 67601 + _____

Phone: (785) 628-7443

Proposed Date of Plugging (if known): August 25, 2009

Payment of the Plugging Fee (K.A.R. 82-3-118) will be guaranteed by Operator or Agent

Date: August 24, 2009 Authorized Operator / Agent: Roger J. Moses Agent: Agent - DIST 4
(Signature)

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

* KCC - Well plugged - KCC