

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING APPLICATION
Please TYPE Form and File ONE Copy

Form CP-1
March 2009
This Form must be Typed
Form must be Signed
All blanks must be Filled

OPERATOR: License #: 5056
Name: F.G. Holl Company, L.L.C.
Address 1: 9431 E. Central, Suite 100
Address 2: _____
City: Wichita State: KS Zip: 67206 + _____
Contact Person: Franklin R. Greenbaum
Phone: (316) 684-8481, Ext. 206

API No. 15 - 047-20,517-0000
If pre 1967, supply original completion date: _____
Spot Description: _____
SE. NW. NW. NE Sec. 13 Twp. 24 S. R. 17 East West
440 Feet from North South Line of Section
440 Feet from East West Line of Section
Footages Calculated from Nearest Outside Section Corner:
 NE NW SE SW
County: Edwards
Lease Name: HAWLEY Well #: 1-13

Check One: Oil Well Gas Well OG D&A Cathodic Water Supply Well Other: _____
 SWD Permit #: _____ ENHR Permit #: _____ Gas Storage Permit #: _____
Conductor Casing Size: _____ Set at: _____ Cemented with: _____ Sacks
Surface Casing Size: 8-5/8" Set at: 259' Cemented with: 225sx Sacks
Production Casing Size: 4-1/2" Set at: 4402' Cemented with: 150sx Sacks

List (ALL) Perforations and Bridge Plug Sets:

Elevation: 2105 (G.L. / K.B.) T.D.: 4410' PBD: 4382' Anhydrite Depth: 1093'
(Stone Corral Formation)

Condition of Well: Good Poor Junk in Hole Casing Leak at: _____
(Interval)

Proposed Method of Plugging (attach a separate page if additional space is needed):

Heavy mud, hulls, cement and plug according to KCC specifications

Is Well Log attached to this application? Yes No Is ACO-1 filed? Yes No

If ACO-1 not filed, explain why:

RECEIVED
AUG 25 2009
KCC WICHITA

Plugging of this Well will be done in accordance with K.S.A. 55-101 et. seq. and the Rules and Regulations of the State Corporation Commission

Company Representative authorized to supervise plugging operations: Mr. Rob Long
Address: 701 E. Santa Fe, Box 308 City: Ellinwood State: KS Zip: 67526 + _____
Phone: (620) 793-0915
Plugging Contractor License #: 31925 Name: Quality Well Service
Address 1: 190 US Highway 56 Address 2: _____
City: Ellinwood State: KS Zip: 67526 + _____
Phone: (620) 727-3410

Proposed Date of Plugging (if known): Not known

Payment of the Plugging Fee (K.A.R. 82-3-118) will be guaranteed by Operator or Agent
Date: 8/21/2009 Authorized Operator / Agent: Loveness Mpanje

Loveness Mpanje
(Signature)
Dietz
PKT

STERLING DRILLING COMPANY
P. O. Box 129
Sterling, Kansas 67579

INVOICE

June 23, 1979

WELL LOG ----- HAWLEY #1-13
Located: 440' FNL, 440' FWL, NE/4, Section 13-24S-
17W, Edwards County, Kansas

OWNER: F. G. Holl, et al
ROTARY DRILLING CONTRACTOR: Sterling Drilling Company

COMMENCED: June 16, 1979
COMPLETED: June 22, 1979

TOTAL DEPTH: 4410'

LOG

0 - 93 Sand
93 - 262 Clay and Shale
262 - 480 Red Beds and Shale
480 - 1093 Sand and Red Bed
1093 - 1107 Anhydrite
1107 - 1802 Shale
1802 - 2134 Shale and Lime Strs.
2134 - 4295 Lime and Shale
4295 - 4410 Lime and Chert

CASING RECORD

Ran 6 joints used 28#, 8 5/8" casing,
247.12' set at 259' K.B. with 225 sacks
60/40 Pozmix with 3% cc. Plug down at
1:15 PM, 6-16-79, by Howco.

Ran 100 joints new 10.5#, 4 1/2" casing,
4391.50' set at 4402' K.B. with 50
sacks Howco Light and 100 sacks Pozmix
with 18% salt, 5# gilsonite, 1/8#
flocels, 1/8# tuffibert and 3/4#
CFR-2 per sack. 250 gal. mud flush
and 20 bbl. salt flush ahead of cement.
Plug down at 9:15 AM, 6-22-79, by Howco.

RECEIVED
AUG 25 2009
KCC WICHITA



Mark Parkinson, Governor Thomas E. Wright, Chairman Michael C. Moffet, Commissioner Joseph F. Harkins, Commissioner

NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)

HOLL, F.G., COMPANY L.L.C.
9431 E CENTRAL STE 100
WICHITA, KS 67206-2563

September 02, 2009

Re: HAWLEY #1-13
API 15-047-20517-00-00
13-24S-17W, 440 FNL 440 FWL
EDWARDS COUNTY, KANSAS

Dear Operator:

This letter is to notify you that the Conservation Division has received your plugging proposal, form CP-1, for the above well and has reviewed the proposal for completeness. The central office will now forward your CP-1 to the district office listed below for review of the proposed plugging method. **Please contact the district office for approval of your proposed plugging method at least five (5) days before plugging the well, pursuant to K.A.R. 82-3-113(b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit in accordance with K.A.R. 82-3-600.**

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well. This notice in no way constitutes authorization to plug the above well by persons not having legal rights of ownership or interest in the well.

This notice is void after March 1, 2010. The CP-1 filing does not bring the above well into compliance with K.A.R. 82-3-111 with regard to the Commission's temporary abandonment requirements.

Sincerely,

Steve Bond
Production Department Supervisor

District: #1
210 E Frontview, Suite A
Dodge City, KS 67801
(620) 225-8888