

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING APPLICATION
Please TYPE Form and File ONE Copy

Form CP-1
March 2009
This Form must be Typed
Form must be Signed
All blanks must be Filled

OPERATOR: License #: 30762
Name: Oil Company of America, Inc.
Address 1: 1200 Main St. Suite # 101
Address 2: _____
City: Hays State: KS Zip: 67601 + _____
Contact Person: Darrel Herl
Phone: (785) 628-3800

KANSAS CORPORATION COMMISSION

API No. 15 - 051-03193-00-00
If pre 1967, supply original completion date: _____
Spot Description: NW/4
SW NW/NW Sec. 13 Twp. 15 S. R. 18 East West
4,290 Feet from North / South Line of Section
4,950 Feet from East / West Line of Section
Footages Calculated from Nearest Outside Section Corner:
 NE NW SE SW
County: Ellis
Lease Name: Leiker Well #: 2

AUG 26 2009
RECEIVED

Check One: Oil Well Gas Well OG D&A Cathodic Water Supply Well Other: _____
 SWD Permit #: _____ ENHR Permit #: _____ Gas Storage Permit #: _____

Conductor Casing Size: _____ Set at: _____ Cemented with: _____ Sacks
Surface Casing Size: 8 5/8" Set at: 1168' Cemented with: _____ Sacks
Production Casing Size: 5 1/2" Set at: 3585' Cemented with: 150 Sacks

List (ALL) Perforations and Bridge Plug Sets:
August 20, 2009, Squeezed off arbuckle open-hole, drilled out to 3589' perforated 9' of arbuckle. No bridge plugs.
Elevation: 2018' (G.L. / K.B.) T.D.: 3589 PBDT: N/A Anhydrite Depth: 1168'
(Stone Corral Formation)

Condition of Well: Good Poor Junk in Hole Casing Leak at: _____
(Interval)

Proposed Method of Plugging (attach a separate page if additional space is needed):
Tie onto 5 1/2" production casing, squeeze w/275 sxs cmt & 400 hulls. Tie onto 8 5/8" x 5 1/2" annulus and squeeze 50 sxs cmt.

Is Well Log attached to this application? Yes No Is ACO-1 filed? Yes No

If ACO-1 not filed, explain why:
Case Morris copied the log adjacent to this well-bore, 50' to the north, the TS Leiker # 9 which was plugged 8/5/2009.

Plugging of this Well will be done in accordance with K.S.A. 55-101 et. seq. and the Rules and Regulations of the State Corporation Commission
Company Representative authorized to supervise plugging operations: Darrel Herl

Address: 1200 Main St. Suite #101 City: Hays State: KS Zip: 67601 + _____
Phone: (785) 628-3800

Plugging Contractor License #: 32810 Name: Professional Pulling Services, LLC
Address 1: PO Box 486 Address 2: _____

City: Hays State: KS Zip: 67601 + _____
Phone: (785) 628-7443

Proposed Date of Plugging (if known): August 26, 2009 10 00 AM

Payment of the Plugging Fee (K.A.R. 82-3-118) will be guaranteed by Operator or Agent
Date: August 24, 2009 Authorized Operator / Agent: Rogena P. Maso Agent
(Signature)

Dist 4
PICT

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202
*KCC - Well plugged - PICT