

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

WM. H. AVERY Governor  
WILLIAM L. MITCHELL Chairman  
JAMES O. GREENLEAF Commissioner  
HARRY G. WILES Commissioner  
RAYMOND B. HARVEY Secretary  
E. EDWARD JOHNSON Gen. Counsel

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita 2, Kansas

8-14-67  
AUG 14 1967  
CONSERVATION DIVISION  
WICHITA, KANSAS

Dear Sir:

Mr. Merkle of D. R. Lauck Oil Co. has this

date requested permission to plug the following described well:

Mr. Merkle guarantees payment of the plugging fee.

Operator's full Name: D. R. Lauck Oil Co.

Complete Address: 301 S. Broadway Wichita, Kansas

Lease Name: Dauwe Well No. 1

Location: NE SE SE Sec. 30 Twp. 10 Rge. 18 (E)(W) X

County Rooks Total Depth 3682 Oil Well     

Gas Well      Input Well      SWD Well      D & A X Lost Hole     

Mr. Merkle was instructed to plug the well as follows:

Gun pits, circulate heavy mud, set cementing plug at 800' and displace  
90 sc cement thru drill pipe. Heavy mud to 210' set cementing plug and  
displace 25 sc cement thru drill pipe. Heavy mud to 40' set cementing  
plug, 1/2 sc hulls and 10 sc cement to base of cellar. Plug rat hole  
with 2 sc cement.

Very truly yours,

Prof. Massup  
Conservation Division Agent