

15-163-21431-0000

State of Kansas

FORM CP-2



JOHN CARLIN
R. C. LOUX
JANE T. ROY
PHILLIP R. DICK
CAROL J. LARSON

Governor
Chairman
Commissioner
Commissioner
Executive Secretary

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

200 Colorado Derby Building
WICHITA, KANSAS 67202

VERBAL PERMIT FORM (To be filed by Plugging Agent)

Dear Sir:

Mr. Bill Draper of Dreiling Oil, Inc. has this date requested permission to plug the following described well:

Operator's Full Name: Rockwood Petroleum Company

Complete Address: 815 Douglas Bldg., Wichita, Ks.

Lease Name: Collins Well No. #1

Location: SW/NW/SE Sec. 28 Twp. 10 Rge. 18 (E) ~~(W)~~

County: Rooks Total Depth: 3675

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereafter indicated: _____

Mr. Bill Draper was instructed to plug the well as follows:

8 5/8"-175' sp. cuc. with 135 sacks cement-2% Gel.-3% Cal. Cl.

Ordered 130 sacks 50/50 posmix-4% Gel.-3% Cal. Cl. and 8 5/8" plug. Spotted with drill stem-with heavy mud between all plugs.

1st plug @ 720' with 70 sacks cement

2nd plug @ 150' with 40 sacks cement

3rd plug-solid bridge of hulls and plug at 40' with 10 sacks cement.

5 sacks cement in rat hole and 5 sacks cement in mouse hole.

Very truly yours,

9-11-81

[Signature]
Conservation Division Agent