

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
7-24-67
JUL 24 1967
STATE CORPORATION COMMISSION
WICHITA, KANSAS

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Lahar of B-B Drlg. Inc. has this date requested permission to plug the following described well:

Mr. Lahar guarantees payment of the plugging fee.

Operator's full Name: Allison & Black

Complete Address: 1415 Wichita Plaza Wichita, Kansas

Lease Name: Sutor Well No. 1

Location: NE SE SW Sec. 5 Twp. 10 Rge. 19 (E)(W) X

County Rooks Total Depth 3798 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Lahar was instructed to plug the well as follows:

Gun pits, circulate heavy mud, set cementing plug at 800' and displace
90 sc cement thru drill pipe, Heavy mud to 210' set cementing plug and
displace 20 sc cement thru drill pipe, Heavy mud to 40' set cementing
plug, 1/2 sc hulls and 8 sc cement to base of cellar. Plug rat hole
with 2 sc cement.

Very truly yours,

R. F. Massey
Conservation Division Agent