

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
1-16-71
JAN 21 1971
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Draper of L. J. Dreiling & Sons has this

date requested permission to plug the following described well:

Mr. Draper guarantees payment of the plugging fee.

Operator's full Name: A. Scott Ritchie

Complete Address: 412 Union Center Bldg., Wichita, Ks.

Lease Name: Pywell Well No. 1

Location: SW NE NW Sec. 6 Twp. 10 Rge. (E)(W) 19

County: Rooks Total Depth 3839' Oil Well

Gas Well Input Well SWD Well D & A XX Lost Hole

Mr. Draper was instructed to plug the well as follows:

Gun pits, circulated heavy mud, set cementing plug at 720' and displace
70 sk cmt thru drill pipe. Heavy mud to 220' set cementing plug and
displace 20 sk cmt thru drill pipe. Heavy mud to 40' set cementing
plug, 1/2 sk hulls and 10 sk cmt to base of cellar.

Very truly yours,

[Signature]
Conservation Division Agent