

State of Kansas



# State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)

245 North Water  
WICHITA, KANSAS 67202

### VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION  
10-12-76  
OCT 12 1976

J. Lewis Brock  
Administrator  
245 North Water  
Wichita, Kansas 67202

CONSERVATION DIVISION  
Wichita, Kansas

Dear Sir:

Mr. Curtis of Duke Drlg. has this

date requested permission to plug the following described well:

Mr. Curtis guarantees payment of the plugging fee.

Operator's full Name: F & M Oil Co., Inc.

Complete Address: 505 Union Center, Wichita, Ks.

Lease Name: Childs Well No. 1

Location: S/2 NW NW Sec. 6 Twp. 10 Rge. (E)(W) 19

County: Rooks Total Depth 3840' Oil Well     

Gas Well      Input Well      SWD Well      D & A XX Lost Hole     

Mr. Curtis was instructed to plug the well as follows:

Gun pits, circulate heavy mud, set 70 sk cmt plug at 720' thru drill

pipe. Heavy mud to 240' set 20 sk cmt plug thru drill pipe. Heavy ~~XXXXXXXXXXXXXXXXXXXX~~

mud to 40' set solid bridge & 10 sk cmt plug to base of cellar.

Very truly yours,

Geo Wassery  
Conservation Division Agent