

**KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING APPLICATION**
Please TYPE Form and File ONE Copy

Form CP-1
September 2003
This Form must be Typed
Form must be Signed
All blanks must be Filled

API # 15 - 191-10710-0001 (Identifier Number of this well). This must be listed for wells drilled since 1967; if no API # was issued,

Indicate original spud or completion date _____

Well Operator: W. D. Short Oil Co., LLC (Owner / Company Name) KCC License #: 33608 (Operator's)

Address: 102 S. River Rd. City: Oxford

State: Ks Zip Code: 67119 Contact Phone: (620) 455 - 3576

Lease: Chamberlain Well #: 3 Sec. 25 Twp. 31S S. R. 2 East West

SE - SW - SW Spot Location / QQQQ County: Sumner

450' Feet (in exact footage) From North / South (from nearest outside section corner) Line of Section (Not Lease Line)

4205' Feet (in exact footage) From East / West (from nearest outside section corner) Line of Section (Not Lease Line)

Check One: Oil Well Gas Well D&A Cathodic Water Supply Well
 SWD Docket # _____ ENHR Docket # _____ Other: _____

Conductor Casing Size: _____ Set at: _____ Cemented with: _____ Sacks

Surface Casing Size: 8-5/8" Set at: 300' Cemented with: surface Sacks

Production Casing Size: 4-1/2" Set at: 2216' Cemented with: no records Sacks

List (ALL) Perforations and Bridgeplug Sets: 1842-1/2'-1847' 1852'-1856' Sand @ 1790 + 4SKS

Elevation: 1161 (G.L. / K.B.) T.D.: 2230 P.B.T.D.: 2230 Anhydrite Depth: _____
pip: ceiling 1020

Condition of Well: Good Poor Casing Leak Junk in Hole (Stone Corral Formation)

Proposed Method of Plugging (attach a separate page if additional space is needed): per KCC Instructions

350 to surface 105 SKS

RECEIVED

SEP 08 2009

KCC WICHITA

Is Well Log attached to this application as required? Yes No Is ACO-1 filed? Yes No

If not explain why? Purchased well with no records or logs, checked KCC for ACO-1

Plugging of this Well will be done in accordance with K.S.A. 55-101 et. seq. and the Rules and Regulations of the State Corporation Commission.

List Name of Company Representative authorized to be in charge of plugging operations: Michael A. Anstine

Phone: (620) 218 - 1822

Address: 102 S. River Rd. City / State: Oxford, Ks 67119

Plugging Contractor: Quality Well Service (Company Name) KCC License #: 31925 (Contractor's)

Address: 190 U.S Highway 56 Phone: (620) 727 - 3410

Proposed Date and Hour of Plugging (if known?): A.S.A.P

Payment of the Plugging Fee (K.A.R. 82-3-118) will be guaranteed by Operator or Agent

Date: 2-16-08 Authorized Operator / Agent: Will Short (Signature)

*Disto
PKT*

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

Quality Well Service, Inc.

190 US Highway 56
Ellinwood, KS 67526

Invoice

| | |
|----------|-----------|
| Date | Invoice # |
| 9/1/2009 | 1106 |

| |
|------------------------------------------------------------------|
| Bill To |
| W. D. Short Oil Co., LLC 102 S. River Rd. Oxford, KS 67119 |

| | | |
|----------|-------|----------------|
| P.O. No. | Terms | Lease Name |
| | Net | Chamberlain #3 |

| Description | Qty | Rate | Amount |
|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|------|--------|-----------|
| Rig Time | 13.5 | 185.00 | 2,497.50T |
| Floor Rental | 1 | 125.00 | 125.00T |
| Sand | 1 | 35.00 | 35.00T |
| Cement | 4 | 9.00 | 36.00T |
| Shots | 2 | 300.00 | 600.00T |
| Torch | 1 | 50.00 | 50.00T |
| Water Truck | 5 | 75.00 | 375.00T |
| Backhoe | 4.5 | 75.00 | 337.50T |
| Out of Town | 1 | 120.00 | 120.00T |
| Phone Calls | 1 | 15.00 | 15.00T |
| Clerical | 1 | 20.00 | 20.00T |
| Wiping Rubber | 1 | 20.00 | 20.00T |
| <p>08/25/09:</p> <p>Drove to location and raised pole. Checked hole; Sanded off bottom. Loaded hole with water; Dug cellar. Unpacked casing head; Set floor. Checked hole; Sand was at 1,790'. Bailed 4 sacks cement with bailer; Pulled slips. Cut surface off 4' below ground; Ripped casing at 1,210', 1,140', and 1,020'. Pipe came free; Pulled casing up to 350'. Swedge in. Drove to motel.</p> <p>08/26/09:</p> <p>Drove to location. Pumped 105 sacks of 100# hulls at 350' to surface. Pulled rest of casing. Tore down floor and rig. Backfilled pit and cellar.</p> | | | |

RECEIVED
SEP 08 2009
KCC WICHITA

| | |
|-------------------------|------------|
| Subtotal | \$4,231.00 |
| Sales Tax (6.3%) | \$266.55 |
| Total | \$4,497.55 |



Mark Parkinson, Governor Thomas E. Wright, Chairman Michael C. Moffet, Commissioner Joseph F. Harkins, Commissioner

NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)

W.D. SHORT OIL CO., LLC
102 S RIVER RD
PO BOX 729
OXFORD, KS 67119-8801

September 15, 2009

Re: CHAMBERLAIN #3
API 15-191-10710-00-01
25-31S-2E, 450 FSL 4205 FEL
SUMNER COUNTY, KANSAS

Dear Operator:

This letter is to notify you that the Conservation Division has received your plugging proposal, form CP-1, for the above well and has reviewed the proposal for completeness. The central office will now forward your CP-1 to the district office listed below for review of the proposed plugging method. **Please contact the district office for approval of your proposed plugging method at least five (5) days before plugging the well, pursuant to K.A.R. 82-3-113(b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit in accordance with K.A.R. 82-3-600.**

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well. This notice in no way constitutes authorization to plug the above well by persons not having legal rights of ownership or interest in the well.

This notice is void after March 14, 2010. The CP-1 filing does not bring the above well into compliance with K.A.R. 82-3-111 with regard to the Commission's temporary abandonment requirements.

Sincerely,

Steve Bond
Production Department Supervisor

District: #2
3450 N. Rock Road, Suite 601
Wichita, KS 67226
(316) 630-4000