

**KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION  
WELL PLUGGING APPLICATION**  
Please TYPE Form and File ONE Copy

Form CP-1  
September 2003  
This Form must be Typed  
Form must be Signed  
All blanks must be Filled

API # 15 - 191-21199 - 0000 (Identifier Number of this well). This must be listed for wells drilled since 1967; if no API # was issued,

Indicate original spud or completion date \_\_\_\_\_

Well Operator: W. D. Short Oil Co., LLC KCC License #: 33608  
(Owner / Company Name) (Operator's)

Address: 102 S. River Rd. City: Oxford

State: Ks Zip Code: 67119 Contact Phone: ( 620 ) 455 - 3576

Lease: Chamberlain Well #: 1 Sec. 25 Twp. 31 S. R. 2  East  West

SE NW NE SW Spot Location / QQQQ County: Sumner

2055 Feet (in exact footage) From North /  South (from nearest outside section corner) Line of Section (Not Lease Line)

1919 Feet (in exact footage) From East /  West (from nearest outside section corner) Line of Section (Not Lease Line)

Check One:  Oil Well  Gas Well  D&A  Cathodic  Water Supply Well  
 SWD Docket # \_\_\_\_\_  ENHR Docket # \_\_\_\_\_  Other: \_\_\_\_\_

Conductor Casing Size: \_\_\_\_\_ Set at: \_\_\_\_\_ Cemented with: \_\_\_\_\_ Sacks

Surface Casing Size: 8-5/8" Set at: 255' Cemented with: surface Sacks

Production Casing Size: 4-1/2" Set at: 2434' Cemented with: no records Sacks

List (ALL) Perforations and Bridgeplug Sets: no records 1842-1856

send @ 1760 + 4SKS pipe recovery 1410

Elevation: 1164 ( G.L. /  K.B.) T.D.: 2456' PBTD: 2160 Anhydrite Depth: \_\_\_\_\_  
(Stone Corral Formation)

Condition of Well:  Good  Poor  Casing Leak  Junk in Hole

Proposed Method of Plugging (attach a separate page if additional space is needed): per KCC Instructions

305 to surface, 100 SKS 100 # hulls

Is Well Log attached to this application as required?  Yes  No Is ACO-1 filed?  Yes  No

If not explain why? Purchased well with no records or logs, checked KCC for ACO-1

**RECEIVED  
SEP 08 2009  
KCC WICHITA**

Plugging of this Well will be done in accordance with K.S.A. 55-101 et. seq. and the Rules and Regulations of the State Corporation Commission.

List Name of Company Representative authorized to be in charge of plugging operations: Michael A. Anstine

Phone: ( 620 ) 218 - 1822

Address: 102 S. River Rd. City / State: Oxford, Ks 67119

Plugging Contractor: Quality Well Service KCC License #: 31925  
(Company Name) (Contractor's)

Address: 190 U.S Highway 56 Phone: ( 620 ) 727 - 3410

Proposed Date and Hour of Plugging (if known?): A.S.A.P

Payment of the Plugging Fee (K.A.R. 82-3-118) will be guaranteed by Operator or Agent

Date: 2-16-08 Authorized Operator / Agent: Walt Short  
(Signature)

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

*Dist 2  
PKT*

*KCC  
PKT  
Per Spud  
Research*

# Quality Well Service, Inc.

190 US Highway 56  
Ellinwood, KS 67526

# Invoice

Date	Invoice #
9/1/2009	1109

Bill To
W. D. Short Oil Co., LLC 102 S. River Rd. Oxford, KS 67119

P.O. No.	Terms	Lease Name
	Net	Chamberlain #1

Description	Qty	Rate	Amount
Rig Time	12.5	185.00	2,312.50T
Floor Rental	1	125.00	125.00T
Sand	1	35.00	35.00T
Cement	4	9.00	36.00T
Shots	1	300.00	300.00T
Torch	1	50.00	50.00T
Water Truck	5	75.00	375.00T
Backhoe	4.5	75.00	337.50T
Out of Town	1	120.00	120.00T
Phone Calls	1	15.00	15.00T
Clerical	1	20.00	20.00T
Wiping Rubber	1	20.00	20.00T
08/26/09:			
Drove to location and raised pole. Checked hole; Sanded off. Loaded hole with water. Dug cellar; Unpacked casing head. Set floor; Checked hole. Sand was at 1,760'; Bailed 4 sacks cement with bailer. Pulled slips; Casing parted. Cut surface off 4' below ground; Screwed casing back together. Ripped casing at 1,410'; Came free. Pulled casing up to 305'; Swedge in. Drove to motel.			
08/27/09:			
Drove to location. Pumped 100 sacks of 100# hulls at 305' to surface; Pulled rest of casing. Tore down floor and rig; Backfilled pit and cellar.			

RECEIVED  
SEP 08 2009  
KCC WICHITA

<b>Subtotal</b>	\$3,746.00
<b>Sales Tax (6.3%)</b>	\$236.00
<b>Total</b>	\$3,982.00



CORPORATION COMMISSION

Mark Parkinson, Governor Thomas E. Wright, Chairman Michael C. Moffet, Commissioner Joseph F. Harkins, Commissioner

**NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)**

W.D. SHORT OIL CO., LLC  
102 S RIVER RD  
PO BOX 729  
OXFORD, KS 67119-8801

September 15, 2009

Re: CHAMBERLAIN #1  
API 15-191-21199-00-00  
25-31S-2E, 2055 FSL 3360 FEL  
SUMNER COUNTY, KANSAS

Dear Operator:

This letter is to notify you that the Conservation Division has received your plugging proposal, form CP-1, for the above well and has reviewed the proposal for completeness. The central office will now forward your CP-1 to the district office listed below for review of the proposed plugging method. **Please contact the district office for approval of your proposed plugging method at least five (5) days before plugging the well, pursuant to K.A.R. 82-3-113(b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit in accordance with K.A.R. 82-3-600.**

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well. This notice in no way constitutes authorization to plug the above well by persons not having legal rights of ownership or interest in the well.

**This notice is void after March 14, 2010. The CP-1 filing does not bring the above well into compliance with K.A.R. 82-3-111 with regard to the Commission's temporary abandonment requirements.**

Sincerely,

Steve Bond  
Production Department Supervisor

District: #2  
3450 N. Rock Road, Suite 601  
Wichita, KS 67226  
(316) 630-4000