

**KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING APPLICATION**
Please TYPE Form and File ONE Copy

Form CP-1
March 2009
**This Form must be Typed
Form must be Signed
All blanks must be Filled**

OPERATOR: License #: 5259
Name: Mai Operations, Inc.
Address 1: P.O. Box 33
Address 2: _____
City: Russell State: Ks. Zip: 67665 + _____
Contact Person: Allen Bangert
Phone: (785) 483-2169

API No. 15 - 163-00920-0001
If pre 1967, supply original completion date: _____
Spot Description: _____
SW SE NE SW Sec. 16 Twp. 10 S. R. 20 East West
1,650 Feet from North / South Line of Section
1,650 Feet from East / West Line of Section
Footages Calculated from Nearest Outside Section Corner:
 NE NW SE SW
County: Rooks
Lease Name: Towns Well #: Cowgill #1

*per
KCC*

Check One: Oil Well Gas Well OG D&A Cathodic Water Supply Well Other: _____
 SWD Permit #: _____ ENHR Permit #: _____ Gas Storage Permit #: _____
Conductor Casing Size: _____ Set at: _____ Cemented with: _____ Sacks
Surface Casing Size: 8 5/8" Set at: 260' Cemented with: Unknown Sacks
Production Casing Size: 4 1/2" Set at: 3774' Cemented with: Unknown Sacks

List (ALL) Perforations and Bridge Plug Sets:
Holes in csg @ 3090-2535' squeeze cemented w/275 sks. Bond log shows cement from 1650' to 260'..

Elevation: 2222' (G.L. / K.B.) T.D.: 3795 PBTD: 3795 Anhydrite Depth: 1705'
(Stone Corral Formation)
Condition of Well: Good Poor Junk in Hole Casing Leak at: _____
(Interval)

Proposed Method of Plugging (attach a separate page if additional space is needed):
Packer & RBP stuck @3400' Tubing backed off @ 2305'. Suspect csg leak between 650'-260' w/ pumping fluid level @ 475'. Dig out bradenhead, Hookup to 4 1/2" csg. Pump csg volume plus 50 sks cement and hulls. Hookup to bradenhead and pump 50sks and hulls.

Is Well Log attached to this application? Yes No Is ACO-1 filed? Yes No
If ACO-1 not filed, explain why:

**RECEIVED
SEP 11 2009
KCC WICHITA**

Plugging of this Well will be done in accordance with K.S.A. 55-101 et. seq. and the Rules and Regulations of the State Corporation Commission
Company Representative authorized to supervise plugging operations: Kent Willson
Address: P.O. Box 33, City: Russell State: Ks. Zip: 67665 + _____
Phone: (785) 483-1683
Plugging Contractor License #: 99996 Name: Allied Cementing
Address 1: P.O. Box 31 Address 2: _____
City: Russell State: Ks Zip: 67665 + _____
Phone: (785) 483-2627

Proposed Date of Plugging (if known): 10-01-09
Payment of the Plugging Fee (K.A.R. 82-3-118) will be guaranteed by Operator or Agent
Date: 09-10-09 Authorized Operator / Agent: _____
(Signature)

*Dist 4
PRT*



CORPORATION COMMISSION

Mark Parkinson, Governor Thomas E. Wright, Chairman Michael C. Moffet, Commissioner Joseph F. Harkins, Commissioner

NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)

MAI OIL OPERATIONS, INC.
8411 PRESTON RD STE 800
DALLAS, TX 75225-5520

September 16, 2009

Re: TOWNS #COWGILL 1
API 15-163-00920-00-01
16-10S-20W, 1650 FSL 1650 FWL
ROOKS COUNTY, KANSAS

Dear Operator:

This letter is to notify you that the Conservation Division has received your plugging proposal, form CP-1, for the above well and has reviewed the proposal for completeness. The central office will now forward your CP-1 to the district office listed below for review of the proposed plugging method. **Please contact the district office for approval of your proposed plugging method at least five (5) days before plugging the well, pursuant to K.A.R. 82-3-113(b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit in accordance with K.A.R. 82-3-600.**

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well. This notice in no way constitutes authorization to plug the above well by persons not having legal rights of ownership or interest in the well.

This notice is void after March 15, 2010. The CP-1 filing does not bring the above well into compliance with K.A.R. 82-3-111 with regard to the Commission's temporary abandonment requirements.

Sincerely,

Steve Bond
Production Department Supervisor

District: #4
2301 E. 13th
Hays, KS 67601
(785) 625-0550