

KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION  
**WELL PLUGGING APPLICATION**  
Please TYPE Form and File ONE Copy

Form CP-1  
March 2009  
This Form must be Typed  
Form must be Signed  
All blanks must be Filled

OPERATOR: License #: 5363  
Name: Berexco, Inc.  
Address 1: P. O. Box 723  
Address 2: P.O. Box 20380, Wichita, KS 67206  
City: Hays State: KS Zip: 67601 + \_\_\_\_\_  
Contact Person: Mark Leiker  
Phone: ( 758 ) 628-6101

API No. 15 - N/A 15-065-01899-00-00  
If pre 1967, supply original completion date: 7/1959  
Spot Description: \_\_\_\_\_  
SE-SE NW Sec. 6 Twp. 10 S. R. 25  East  West  
2,310 Feet from  North /  South Line of Section  
2,970 Feet from  East /  West Line of Section  
Footages Calculated from Nearest Outside Section Corner:  
 NE  NW  SE  SW  
County: Graham  
Lease Name: Gra-Sher Well #: GA-1

Check One:  Oil Well  Gas Well  OG  D&A  Cathodic  Water Supply Well  Other: \_\_\_\_\_  
 SWD Permit #: \_\_\_\_\_  ENHR Permit #: \_\_\_\_\_  Gas Storage Permit #: \_\_\_\_\_  
Conductor Casing Size: N/A Set at: \_\_\_\_\_ Cemented with: \_\_\_\_\_ Sacks  
Surface Casing Size: 8 5/8 Set at: 203 Cemented with: 125 Sacks  
Production Casing Size: 5 1/2" Set at: 4038 Cemented with: 500 gallons latex Sacks

List (ALL) Perforations and Bridge Plug Sets:

Open hole 4038-4044, CIBP at 4020'. Perforations 4000-4003 CIBP at 3990, perforations 3970-3972, CIBP at 3960', perforations 3506-08, squeezed w/100 saks then re-perforate 3906-3908.

Elevation: 2574 ( G.L. /  K.B.) T.D.: 4044 PBTD: 3960 Anhydrite Depth: 2175  
(Stone Corral Formation)

Condition of Well:  Good  Poor  Junk in Hole  Casing Leak at: \_\_\_\_\_  
(Interval)

Proposed Method of Plugging (attach a separate page if additional space is needed):

Run tubing to 3200' pump 8 saks jell followed by 50 saks cement. 200# hulls, pull to 2200' pump 100 saks cement, pull to 1325' circulate cement to surface w/150 saks. TOH and top off. Plugging orders from Case Morris.

Is Well Log attached to this application?  Yes  No Is ACO-1 filed?  Yes  No

If ACO-1 not filed, explain why:

N/A

RECEIVED  
SEP 14 2009  
KCC WICHITA

Plugging of this Well will be done in accordance with K.S.A. 55-101 et. seq. and the Rules and Regulations of the State Corporation Commission

Company Representative authorized to supervise plugging operations: Mark Leiker  
Address: P.O. Box 723 City: Hays State: KS Zip: 67601 + \_\_\_\_\_  
Phone: ( 785 ) 628-6101  
Plugging Contractor License #: 5363 Name: Berexco, Inc.  
Address 1: P.O. Box 723 Address 2: P.O. 20380 Wichita, KS 67206  
City: Hays State: KS Zip: 67601 + \_\_\_\_\_  
Phone: ( 785 ) 628-6101

Proposed Date of Plugging (if known): After corn is cut.

Payment of the Plugging Fee (K.A.R. 82-3-118) will be guaranteed by Operator or Agent

Date: 9/9/09 Authorized Operator / Agent: Mark Leiker  
(Signature)

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

DATA 4  
PKT



Mark Parkinson, Governor Thomas E. Wright, Chairman Michael C. Moffet, Commissioner Joseph F. Harkins, Commissioner

**NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)**

BEREXCO, INC.  
PO BOX 20380  
WICHITA, KS 67208-1380

September 21, 2009

Re: GRA-SHER #GA-1  
API 15-065-01899-00-00  
6-10S-25W, 2310 FNL 2970 FEL  
GRAHAM COUNTY, KANSAS

Dear Operator:

This letter is to notify you that the Conservation Division has received your plugging proposal, form CP-1, for the above well and has reviewed the proposal for completeness. The central office will now forward your CP-1 to the district office listed below for review of the proposed plugging method. **Please contact the district office for approval of your proposed plugging method at least five (5) days before plugging the well, pursuant to K.A.R. 82-3-113(b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit in accordance with K.A.R. 82-3-600.**

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well. This notice in no way constitutes authorization to plug the above well by persons not having legal rights of ownership or interest in the well.

**This notice is void after March 20, 2010. The CP-1 filing does not bring the above well into compliance with K.A.R. 82-3-111 with regard to the Commission's temporary abandonment requirements.**

Sincerely,

Steve Bond  
Production Department Supervisor

District: #4  
2301 E. 13th  
Hays, KS 67601  
(785) 625-0550