

15-163-19418-0000

STENCILED K. G. S. LIBRARY

JAN 13 1962

ORIGINAL

DRILLERS LOG
TOMLINSON-KATHOL, INC.
1 HAMEL
C N/2 N/2 NW, SEC. 5-10S-19W
ROOKS COUNTY, KANSAS

5-10-19W
C N/2 N/2 NW

Contractor - Tomlinson-Kathol, Inc.

Commenced: 9/5/61
Completed: 9/16/61
Elevation: 2223 KB

32 Bopel

<u>From</u>	<u>To</u>	<u>Description</u>	<u>Remarks</u>
0	45	Sand & Clay	
45	143	Clay	
145	149	Shale	149' 8-5/8" Surf. Csg. w/125 Sacks
149	226	Shale	Cement
735	850	Sand, Sand Clay	
850	1633	Shale	
1633	1680	Anhydrite	
1680	2138	Shale	
2138	2250	Lime	
2250	2498	Lime, Shale	
2496	2588	Shale & Lime	
2588	3366	Lime & Shale	
3366	3575	Lime	
3707	3746	Chert & Shale	
3746	3767	Simpson	Topeka 3211
3767	3769	Arbuckle	Heebner 3419
3769		Total Depth	Toronto 3437
			Lansing 3457
			Conglomerate 3698
			5 1/2" Casing 3767

I certify to the best of my knowledge and belief, the above represents a true and accurate Driller's Log record of the captioned well.

Gerald J. Kathol

State of Kansas)
) SS:
County of Sedgwick)

10/24/61
16/10/0

Subscribed and sworn to before me this 24th day of October, 1961.

Esther Lamone, Notary Public

My Commission Expires: 1/19/65

STATE OF KANSAS

FEB 02 1965

"OWWO"

CO: TOMLINSON OIL CO., INC.

WELL #1 HAMEL

IP: SWDW 1110-20, 1150-75

NEW INFO: MICT - SWB DWN, FL 900' DWN, SWB DWN 1600', PF 20/1110-20, 50/1150-75, SWB/5hrs, FROM 400' FL @ 200' REC LOTS SD, INJ RATE SATIS, SWDW

WICHITA KANSAS