

15-163-00037-0001

ORDWAY E-2

O.W.W.O.

COMPLETED JUNE, 1958

Davis Bros.
Ordway E-2 O.W.W.O. Initial completion was 4-26-46
NW NW 1/4 Section 20-10S-18W
Rooks County, Kansas

Elevation 2168' D.F.
Elevation from the Bradenhead 2162'
T.D. 3842'

Casing Record:

13" @ 120' No record of cement used
5 1/2" 14# J-55 SH @ 3820' w/200 sax
No D.V. Tool used

FORMATION TOPS

Topeka	3153'	(- 985)
Heebner	3371'	(-1203)
Toronto	3397'	(-1229)
Lansing	3415'	(-1247)
Base K.C.	3641'	(-1473)
Conglomerate	3691'	(-1523)
Simpson	3795'	(-1627)
Arbuckle	3815'	(-1647)
T.D.	3835'	(-1667)

RECEIVED
STATE CORPORATION COMMISSION

OCT 7 1964

CONSERVATION DIVISION
Wichita, Kansas

June 15, 1958

Moving in cable tools. Rigged up swabbed hole down and logged. Company time 12 hrs.

June 16, 1958

Perforated Chaetetes Zone (Marmaton) from 3666' - 3670'. Let stand for 1/2 hour and ran bailer at 30 minute intervals, for 1 1/2 hours. Recovered 2 gallons thin drilling mud on each run with fair show of oil.

Acidized w/500 gallons Non-E Acid. Displaced all of the acid at pressures ranging from 100# - 250# in 2 hours. Zero pressure in 15 minutes. Let acid stand 1 hour and then swabbed the hole down. Recovered 3 bbls. of fluid, 80% water in the first hour after swabbing hole down. Company time 12 hrs.