

15-163-01905-0000

Pick Well No. 6

SE NW SE  
Sec. 7-10S-19W  
Rocks County, Kansas

Contractor: The R. L. Hine Drilling Company  
Started: 6/20/50 Finished: 7/2/50

Reamed	0 - 41	
Sand, Shale, Shells	41 - 975	
Shale, Sand, Shells	975 - 1508	Syfo @ 1000' -1°
Shale & Shells	1508 - 1622	Syfo @ 1500' O.K.
Anhydrite	1622 - 1835	8-5/8" csg. @ 1635' w/ 800 Sz.
Reamed	40 - 530	
Reaming	530 - 1380	
Reamed	1380 - 1635	
Anhydrite	1635 - 1670	
Sand & Red Red	1670 - 1725	
Shells & Shale	1725 - 2125	Syfo @ 2000' 1/2°
Lime, Shale, Shells	2125 - 2575	
Lime & Shale	2575 - 2760	
Lime	2760 - 2905	
Lime & Shale	2905 - 3355	Syfo @ 3000' 1°
Lime	3355 - 3745	
Shale & Lime	3745 - 3790	T.D. 5 1/2" csg. @ 3790

Top Anhydrite	1621
Heobner	3438
Lansing	3475
Arbuckle	3789

State of Kansas )  
County of Sedgwick ) ss

I, E. H. Sloyer, do hereby certify that the above is a true and accurate log of the Pick Well No. 6, located in the SE NW SE of Sec. 7-10S-19W, Rocks County, Kansas.

E. H. Sloyer  
Secretary

Subscribed to and sworn before me this 7th day of July, 1950

My commission expires Dec. 29, 1952

R. M. Green  
Notary Public