

KEWANEE OIL COMPANYWest Kansas District

Well Record: Catudal "A" #2

Location: NE SW NE Sec. 14-10S-19W, Rooks County, Kansas.

Elevation: 2085 RB.

Drilling Commenced: 1-27-46

Drilling Completed: 2-17-46

Completion Date: 4-26-46

Perforations: 3357-61' with 12 shots      PBTB: 3365'.

Initial Treatment: None

Initial Potential: 550 BO, 30% water, on pump.

RECEIVED  
STATE CORPORATION COMMISSION  
AUG 7 1970  
CONSERVATION DIVISION  
Wichita, Kansas

FORMATION TOPS (SAMPLES)

Anhydrite	1434	+ 651
Topeka	3023	- 938
Lansing-Kansas City	3274	-1189
Base Kansas City Lm.	3501	-1416
Conglomerate	3518	-1433
Simpson	3547	-1462
Arbuckle	3578	-1493
TD	3581	-1496

CASING RECORD

1440' (36 joints) Armco 8-5/8" casing set @ 1437' and cemented with 700 sacks bulk Fortland and 7 sacks CC.

114 joints 5-1/2", 147 SS J casing @ 3578' and cemented with 200 sacks.

COMPLETION RECORD

Perforated 3369-72' with 7 shots - 1160' water with trace of oil in 4 hours. Set LW BP @ 3365-68' and swabbed hole dry. Perforated 12 shots 3357-61'.

WORKOVER RECORD

10-21-47

Well tested 41 BOPD and 350 BWPD prior to PB. Set LW plug @ 3346-50', shut off O.K. Perforated with 57 shots 3313-19', tested 1 gal. oil and water per hour. Acidized with 500 gallons, 2,000 gallons, 5,000 gallons. Placed back on pump and tested 40 BOPD, 60% water.