



ROBERT B. DOCKING Governor  
DALE E. SAFFELS Chairman  
JULES V. DOTY Commissioner  
JAMES O. GREENLEAF Commissioner  
RAYMOND B. HARVEY Secretary  
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION  
1-18-71  
JAN 18 1971  
CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Ehrlich of Murfin Drlg. has this

date requested permission to plug the following described well:

Mr. Ehrlich guarantees payment of the plugging fee.

Operator's full Name: Thunderbird Drlg., Inc.

Complete Address: Box 18412 Wichita, Ks.

Lease Name: Sutor Well No. 1

Location: W/2 SW SW Sec. 14 Twp. 10 Rge. (E)(W) 19

County: Rooks Total Depth 3720' Oil Well

Gas Well  Input Well  SWD Well  D & A XX Lost Hole

Mr. Ehrlich was instructed to plug the well as follows:

Gun pits, circulate heavy mud, set cementing plug at 850' and displace

70 sk cmt thru drill pipe. Heavy mud to 275' set cementing plug and

displace 25 sk cmt thru drill pipe. Heavy mud to 40' set cementing

plug, 1/2 sk hulls and 10 sk cmt to base of cellar.

Very truly yours,

Leo J. Messer  
Conservation Division Agent