

15-163-30164-0000

FORM - CP-2
Rev. 9-8-64

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Fickle of Red Tiger Drilling Co. has this date requested permission to plug the following described well:

Mr. Fickle guarantees payment of the plugging fee

Operator's full Name: Frontier Oil Company

Complete Address: 1720 Wichita Plaza Wichita, Kansas

Lease Name: Dick Well No. 3

Location: NW NW NW Sec. 17 Twp. 10 Rge. 19 (E)(W) X

County Rooks Total Depth 3778 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Fickle was instructed to plug the well as follows:

RTD 3778 8 5/8 set at 219 FT. cwl40 sc cement.

Gun pits, circulate heavy mud, set cementing plug at 540 Ft. and

displace 20 sc cement thru drill pipe. Heavy mud to 210 Ft. set

cementing plug and displace 20 sc cement thru drill pipe. Heavy

mud to 40 Ft. set cementing plug, 1/3 sc hulls, and 10 sc cement

to base of cellar.

Very truly yours,

Geo Massey
Conservation Division Agent

RECEIVED
STATE CORPORATION COMMISSION

6-24-66
JUN 24 1966

CONSERVATION DIVISION
WICHITA, KANSAS