

15-163-20764-0000

State of Kansas

FORM CP-2



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

245 North Water
WICHITA, KANSAS 67202

VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
7-23-78
JAN 23 1978
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
245 North Water
Wichita, Kansas 67202

Dear Sir:

Mr. Wagner of Red Tiger Drlg. has this date requested permission to plug the following described well:

Mr. Wagner guarantees payment of the plugging fee.

Operator's full Name: Frontier Oil Co.

Complete Address: 1720 KSB&T Bldg., Wichita, Ks.

Lease Name: Dick Well No. 5

Location: SE NE NW Sec. 17 Twp. 10 Rge. (E)(W) 19

County: Rooks Total Depth 3780' Oil Well

Gas Well Input Well SWD Well D & A XX Lost Hole

Mr. Wagner was instructed to plug the well as follows:

Gun pits, circulate heavy mud, set 70 sk cmt plug at 660' thru drill pipe. Heavy mud to 240' set 20 sk cmt plug to base of cellar. Heavy mud to 40' set solid bridge & 10 sk cmt plug to base of cellar.

Very truly yours,

Leo Massey
Conservation Division Agent