

State of Kansas



ROBERT B. DOCKING Governor  
 DALE E. SAFFELS Chairman  
 JULES V. DOTY Commissioner  
 JAMES O. GREENLEAF Commissioner  
 RAYMOND B. HARVEY Secretary  
 JACK GLAVES Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
 STATE CORPORATION COMMISSION  
 10-22-68  
 OCT 22 1968  
 CONSERVATION DIVISION  
 Wichita, Kansas

J. P. Roberts  
 Administrator  
 500 Insurance Building  
 Wichita, Kansas 67202

Dear Sir:

Mr. Miller of Graves Drlg. has this

date requested permission to plug the following described well:

Mr. Miller guarantees payment of the plugging fee.

Operator's full Name: John C. Graves, Et al

Complete Address: 505 Union Center Wichita, Ks.

Lease Name: Berland Well No. 1

Location: N/2 N/2 NE Sec. 19 Twp. 10 Rge. 19 (E)(W) X

County: Rooks Total Depth 3857 Oil Well

Gas Well  Input Well  SWD Well  D & A X Lost Hole

Mr. Miller was instructed to plug the well as follows:

Gun pits, circulate heavy mud, set cementing plug at 800' and displace  
70 sc cement thru drill pipe. Heavy mud to 210' set cementing plug and  
displace 20 sc cement. Heavy mud to 10' set cementing plug, 1/2 sc hulls  
and 10 sc cement to base of cellar. Plug rat hole with 2 sc cement.

Very truly yours,

Geo. Massey  
 Conservation Division Agent